# POST-APPOINTMENT BIM EXECUTION PLAN (BEP) FOR CONSTRUCTION and AS-BUILT

Prepared by

BIM Execution Plan Page 1 of 60

# **Document Revision Tracking**

Issue Date	Notes	
2025-08-25	First Issuance	

BIM Execution Plan Page 2 of 60

# **Contents**

1.	BIM Execution Plan Overview	4
2.	Project Information	7
3.	Project Information Functions	8
4.	Information Delivery Strategy	8
5.	BIM Use, Goals & Deliverables	12
6.	Project Information Production Methods and Procedures	15
7.	Project Information Standards	20
8.	Software, Hardware, IT Infrastructure and Training	33
9.	BIM Team Resources, Competency and Training	38
10.	Quality Assurance	45
11.	Handover Procedures	53
Appe	endix A – Master Information Delivery Plan (MIDP)	54
Appe	endix B –Task Information Delivery Plan (TIDP)	55
Appe	endix C – LOD Matrix	56
Appe	endix D – Clash Detection Matrix	57
Appe	endix G – Model File List	58
Appe	endix H – Model Compliance Check Template	58

#### 1. BIM Execution Plan Overview

To successfully implement Building Information Modeling (BIM) on this project, the project team has developed this detailed BIM Project Execution Plan. The BIM Project Execution Plan defines uses for BIM on the project (e.g. BIM coordination, and drawing production), along with a detailed design of the process for executing BIM throughout the project life-cycle.

This document is prepared by to define BIM uses & deliverables, BIM implementation protocol, BIM standards, BIM management and procedure as the Construction (and As-built) Stage BIM Project Execution Plan (BEP). The purpose of this document is to plan and manage BIM implementation to ensure an effective project information sharing and a collaborative design coordination among the Lead Contractor, design consultants and project stakeholders.

This document will be submitted with the agreement from Appointing Party / Client prior to adoption to use.

This document will be continuously updated as the project evolves during project life-cycle, to reflect the appropriate BIM progress and accommodate the project needs. Such updates to this BEP will be made with agreement from and appointed BIM Manager.

This document shall be developed with references from Design Stage BEP, if available, transferred from the

This BEP shall be subject to be reviewed and checked quarterly or as requested by the BIM Auditor and / or the Client.

# 1.1 **Guidelines and Standards**)

BIM Standards	Publication	Date of Publication
Annex To Appendix E, Pre-Contract BIM Execution Plan Template	MTR	03/2022
MTR Naming Standard, Revision March 2022	MTR	09/2022

BIM Execution Plan Page 4 of 60

PAS 1192-6:2018 Specification for collaborative sharing and use of structured Health and Safety information using BIM	International Organization for Standardization (ISO)	02/2018
BD Guidelines for Using Building Information Modelling in GBP Submissions (2019)	Buildings Department (BD)	2019
HK SAR Development Bureau DEVB TC(W) No. 02/2021 Adoption of Building Information Modelling for Capital Works Projects in Hong Kong (December 2021)	Development Bureau (DEVB)	09/2021
CIC BIM Guide for using BIM in generation of MEP digital drawings for statutory submissions	Construction Industry Council (CIC)	2021
CIC BIM Standards General 2021	Construction Industry Council (CIC)	Version 2.1 - 2021
CIC BIM Standards Architecture and Structural Engineering	Construction Industry Council (CIC)	Version 2.1 - 2021
CIC BIM Standards for Mechanical, Electrical and Plumbing	Construction Industry Council (CIC)	Version 2 - 2021
CIC BIM Standards for Underground Utilities	Construction Industry Council (CIC)	Version 2 - 2021
CIC Production of BIM Object Guide - General Requirements	Construction Industry Council (CIC)	2021
CIC BIM Standards for Preparation of Statutory Plan Submissions	Construction Industry Council (CIC)	Vision 1.1 2021
Statutory Submission	Buildings Department (BD), Water Authority (WSD) & Construction Industry Council (CIC)	2022

BIM Execution Plan Page 5 of 60

ISO 19650-2:2018 Organization and digitization of information about buildings and civil engineering works, including building information modelling (BIM) — Information management using building information modelling — Part 2: Delivery phase of the assets	International Organization for Standardization (ISO)	12/2018
ISO 19650-3:2020 Organization and digitization of information about buildings and civil engineering works, including building information modelling (BIM) - Information management using building information modelling - Part 3: Operational phase of the assets.	International Organization for Standardization (ISO)	06/2020
BS 1192-4:2014 Collaborative production of information. Fulfilling employer's information exchange requirements using COBie. Code of practice.	International Organization for Standardization (ISO)	09/2014
ISO 19650-5:2020 Organization and digitization of information about buildings and civil engineering works, including building information modelling (BIM) — Information management using building information modelling — Part 5: Security-minded approach to information management	International Organization for Standardization (ISO)	06/2020
Information Protocol to support BS EN ISO 19650-2 the delivery phase of assets Edition 2 September 2020 (UK BIM Framework and CIC).	Centre for Digital Built Britain (CDBB)	06/2020

BIM Execution Plan Page 6 of 60

# 2. **Project Information** 2.1. Project Description Project Name 2.2. Project Detail Employer Client MTR Contract No MTR Contract No Submitted By Ву

Date

2025/08/28

BIM Execution Plan Page 7 of 60

# 3. Project Information Functions

The following BIM software platforms will be used across the project team for all submissions.

No	Function / form	Originating application	Version
1.	Information Model Submissions	Autodesk Navisworks Manage / original authoring platform	2022
2.	Design authoring of buildings and other vertical facilities	Autodesk Revit (Architecture, Structure, MEP)	2022
3.	Design authoring of civil and other linear facilities	Autodesk Civil 3D	2022
4.	Alignment design	N/S	N/S
5.	Federation, coordination and design review	Autodesk Navisworks Manage / Autodesk Construction Cloud (Formerly known as BIM 360)	2022
6.	Construction planning, sequencing and simulation	Synchro	2022
7.	Presentation of 4D animations, videos, analyses, etc.	Synchro	2022
8.	Drawings	Autodesk Revit	2022
9.	Drawings	Autodesk Civil 3D	2022
10.	Clash Analysis reports	Autodesk Navisworks Manage	2022
11.	Schedules, Tables	N/S	Latest version
12.	Document production	MS Office (Word, PowerPoint, Excel, etc.)	Latest version
13.	Document reviewing and commenting	MS Office (Word, PowerPoint, Excel, etc.)	Latest version
14.	Images	.jpg, .png	Latest version

# 4. Information Delivery Strategy

To ensure that the information modelling workflow defined under section table below, Client's

Common Data Environment is compliant, at all times, with the requirements of C11286, checks will be made

by the BIM team of


on the timeliness of information model uploads,

adherence to the LOD standards set out in this document and the completion of DOC requirements by all of
the BIM-related supply chain on the project. Checklists will be developed to assess such compliance and

BIM Execution Plan Page 8 of 60

criteria established to identify potential non-compliancy. KPIs may also be developed to allow early identification of weak links in the supply chain where non-compliancy is a risk. Any non-compliancy will trigger immediate remedial action by the Tyfron Solutions.

The following checks as shown belo will be performed to assure adherence to the quality of the BIM models are checked and comply with BIM standards and procedures.



# Validation Checklist

Level of Check	Action	Software	Checked
Issue for Coordination	BIM Checklist sign off by discipline coordinator	Autodesk Model Review, manual checks	

# **BIM Checklist**

BIM Execution Plan Page 9 of 60

ltem	Checked
CAD standard check (compliance with agreed CAD standards)	
Models at the correct Origin and Orientation of project base point	
Models must be at 1:1 Scale, that is, no dimensions changed without changing the underlying model geometry	
2D linework must be aligned to its associated 3D surface at correct orientation, elevation and origin	
There must be no duplicate objects	
There shall be no 'custom' objects, that is, objects created by the user that are not approved or part of the Originators and/or Project library	
Models must be stand-alone project files with all linked data bound or removed	
All 'hidden', 'scrap', 'temporary' or redundant objects / geometry / linework must be deleted	
All author created views, sheet layout data (title blocks, annotation etc) and templates must be removed with the exception of the "model title view"	
All data not authored by the originator must be removed (e.g. shared grid file linked into architectural model)	
Model integrity must be correct (e.g. columns meet beams and slabs - no gaps)	
All objects must have the extended properties completed against the required Level of Detail	
All object properties must be spelt and formatted correctly and consistently	
All model files must have the correct filename and metadata	
Check that the model is using the current shared parameters, and keynotes files	

Checks	Definitions	Responsible Parties	Methodologies	Frequency
LOD-G Proposed	Ensure the geometry of the object elements are modelled to	BIM Coordinators	Visual check of 3% of modelled objects	Bi-Monthly
	the proposed	BIM Project Manager	Visual check of 5% of modelled objects	Before the major submission stage of the deliverables

BIM Execution Plan Page 10 of 60

LOD-I Proposed	Ensure the attributes of the object elements are created/entered to	BIM Coordinators	Visual check of 3% of modelled objects using exported table	Bi-Monthly
	the proposed format and contents	BIM Project Manager	Visual check of 5% of modelled objects using exported table	Before the major submission stage of the deliverables
Geometrical accuracy and engineering standard compliance	Ensure the objects are modelled to the exact size, location and orientation according to the LoD-G proposed.	BIM Coordinators	Overlay of design drawings, and random annotation of XYZ positions.	Bi-Monthly
		BIM Coordinators	Random check on design dimension and engineering requirements	Before the major submission stage of the deliverables
Naming Convention	Ensure the file name, non-system object names follow the proposed standard	BIM Coordinators	Visual Check	Monthly
File format	Ensure the BIM models are created with the proposed file format and version	BIM Coordinators	Random file checks	Monthly
Modelling Methodologies	Ensure the BIM objects are created with the proposed	BIM Coordinators	Visual check of 3% of modelled objects	Bi-Monthly
modelling methodologies		BIM Project Manager	Visual check of 5% of modelled objects using exported table	Before the major submission stage of the deliverables
Project Basepoints	Ensure the reference point of each model comply	BIM Project Manager	Visual check of project basepoints	First week after the model file is created

# **Data Security**

ISO 19650-5:2020 standard, General Conditions of Employment and CDE workflows shall be followed.

BIM Execution Plan Page 11 of 60

Individuals from the Contractor's team and their supply chain participating in the project will have to sign a company-level Non-Disclosure Agreement to ensure they will not make available any confidential and/or sensitive information to individuals that are not involved in the project.

All BIM-related documents shall be uploaded to the Client's and Contractor's CDE for sharing among all parties involved in the project during construction stage. Documents on the CDE shall be backed-up at a maximum interval of bi-weekly, unless otherwise stated. Access to CDE will be granted to individuals according to their CDE accounts registered with professional email addresses. Access is granted to each individual to only the areas on the CDE that are required to facilitate their work scope.

To avoid any possible data corruption or data misuse, the adopted CDE platform, ACC (Formerly known as BIM 360) will provide adequate data security and regular file backup. ACC cannot be accessed without cloud-based usernames and passwords, and prior email invitation from the BIM team leader i.e., the administrator of the CDE platform, will be required.

Members invited to ACC will have access to folders where user access rights are allocated by the administrator. All files on ACC will be stored in the cloud servers hosted by the service provider Amazon Web Services, which are located at a secured data centre protected from unauthorized access and environmental hazards.

The Contractor shall ensure that the computers used for accessing the CDE meet the minimum-security requirements of the Client as below, unless otherwise directed by the Project Manager:

- (a) All applicable security patches are installed and up to date
- (b) Antivirus software is running with up to date virus signature.

The Contractor proposes a workflow to monitor Information Security Risks (ISR) as follows:




Figure 1 – Workflow of Information Security Risks

#### **5.** BIM Use, Goals & Deliverables

BIM Execution Plan Page 12 of 60

\*Grey colour indicate BIM uses not in use in this contract.

The Information Model will be utilised for the following Uses in the different Project Phase as follows:

	Information Model Use	Construction	Testing & commissioning	Project close-out
1	Design Authoring	Υ		
2	Design Review	Υ		
3	Project Deliverables (incl. Drawings)	Υ	Υ	
4	Existing Conditions Model	Υ	Υ	
5	Sustainability Evaluation	Υ	Υ	Υ
6	Site Analysis			
7	Space Programming			
8	Cost Estimation (5D Model)	Υ		
9	Spatial Coordination (3D)	Υ		
10	Engineering Analysis	Υ		
11	Facility Energy Analysis	Υ		
12	Building Code Validation			
	BI BI : (4B			
13	Phase Planning (4D Model)	Υ		
14	Digital Fabrication	Υ		
15	Site Utilisation Planning	Υ		
16	3D Control and Planning	Υ		
17	3D Construction Coordination	Υ		
18	Construction System Design	Υ		

BIM Execution Plan Page 13 of 60

19	Construction Quality Management	Υ		
20	As-Built Model	Υ	Υ	Υ
21	Maintenance Scheduling	Υ	Υ	Υ
22	Project Systems Analysis		Υ	Υ
23	Space Management and Tracking		Υ	Υ
24	Asset Information Model	Υ	Υ	Υ
25	Sales and Marketing	Υ	Υ	Υ
26	Heritage Information Modelling		Y	Υ

Y = BIM shall be used to generate Contract data for the highlighted function. .\*Grey colour indicate BIM uses not in use for the contractor

# **Project Deliverables**

Project Deliverable Items	Checked by	Reference
BIM Project Execution Plan		GS/001/A3/G18.2.1 e.
BIM Progress Report		GS/001/A3/G9.4.1
Construction Stage BIM Model		GS/001/A3/G18.2.1 f.
Clash Report		GS/001/A3/G18.2.1 g.
Federated Models		GS/001/A3/G18.2.1 y.
As-built BIM Model		GS/001/A3/G18.2.1 b.
4D Phase Planning Model		GS/001/A3/G18.6.38- 39
Digital Fabrication		GS/001/A3/G18.6.44- 46
CSD/SEM Drawings		GS/001/A3/G18.2.1 v.
Shop Drawing (if any)		GS/001/A3/G18.2.1 v.

# Coordination Schedule

BIM Execution Plan Page 14 of 60

1286 - BIM and D	esign Time Frame (Draft Version)					Color Legend		Task Completed			Updated on 1 Dec
								Task Overdue			
Location	Federated BIM Model	Item	Area Concerned	Revised Acceptance Programme for Construction Works	Work Programme for	Federated BIM Mode	Control of the State of the Sta	Target settled date, finalization (	C)	Issues/problem cut	AND DESCRIPTION OF THE PARTY OF
				(Oct 2023)	Construction (A)	(B)= Approx. Days b	efore (A)	(C)= Approx. Days be	efore (B)	(D)= Approx. Days	before (C)
		AL_2	Pier 1 Pier Cap Commencement	25 May 2024	25 May 2024	25 Feb 2024	90	26 Jan 2024	30	27 Dec 2023	30
		AL_3	Pier 1 Commencement	12 Jun 2024	12 Jun 2024	14 Mar 2024	90	13 Feb 2024	30	14 Jan 2024	30
	BIM Structure (rebar, SEM,	AL_4	Pile Cap & Base Slab at -3.4mPD & Wall Commencement	10 Jul 2024	10 Jul 2024	11 Apr 2024	90	12 Mar 2024	30	11 Feb 2024	30
	Arch, BS)	AL_5	Staircase from -3.4mPD to + 6.95mPD Commencement	21 Oct 2024	21 Oct 2024	23 Jul 2024	90	23 Jun 2024	30	24 May 2024	30
		AL_6	Roof of Adit & Concourse at +2.7 mPD commencement	21 Oct 2024	21 Oct 2024	23 Jul 2024	90	23 Jun 2024	30	24 May 2024	30
		AL_7	Wall & Staircase from +6.95mPD to 13.11mPD	27 Nov 2024	27 Nov 2024	29 Aug 2024	90	30 Jul 2024	30	30 Jun 2024	30
roach Lobby		AL_8	Structural Steel Erection commencement	23 Jan 2025	23 Jan 2025	25 Oct 2024	90	25 Sep 2024	30	26 Aug 2024	30
and Pier 1	BIM (BS, ABWF) for internal & external	AL_9	ABWF & BS Works commencement	11 Mar 2025	11 Mar 2025	11 Dec 2024	90	11 Nov 2024	30	12 Oct 2024	30
		AL 9a	Cladding	11 Mar 2025	11 Mar 2025	11 Dec 2024	90	11 Nov 2024	30	12 Oct 2024	30
	ABWF (Long Lead Items)	AL 9b	Glazing / Curtain Wall	2 Apr 2025	2 Apr 2025	2 Jan 2025	90	3 Dec 2024	30	3 Nov 2024	30
		AL_9c	Louvre / Window	2 Apr 2025	2 Apr 2025	2 Jan 2025	90	3 Dec 2024	30	3 Nov 2024	30
	BS (Long Lead Items)	AL 9d	Lift	17 Apr 2025	17 Apr 2025	17 Jan 2025	90	18 Dec 2024	30	18 Nov 2024	30
		AL_9e	Escalator	23 Jun 2025	23 Jun 2025	25 Mar 2025	90	23 Feb 2025	30	24 Jan 2025	30
	BIM (SEM & BS) for external works & reinstatement	AL_10	External Pipe and drain commencement	2 Jan 2025	2 Jan 2025	4 Oct 2024	90	4 Sep 2024	30	5 Aug 2024	30
	BIM (rebar & SEM)	FB 11	ELS installation commencement	8 Apr 2024	8 Apr 2024	9 Jan 2024	90	10 Dec 2023	30	10 Nov 2023	30
		FB_12	Pile Cap (PC2 & PC3)	17 May 2024	17 May 2024	17 Feb 2024	90	18 Jan 2024	30	19 Dec 2023	30
		FB 13	Pier 2 & 3 Commencement	6 Jun 2024	6 Jun 2024	8 Mar 2024	90	7 Feb 2024	30	8 Jan 2024	30
		FB 13a	Bearing	6 Jun 2024	6 Jun 2024	8 Mar 2024	90	7 Feb 2024	30	8 Jan 2024	30
		FB_14	Footbridge : Segment 1 (Steelworks Fabrication Drawings)	8 Apr 2024	8 Apr 2024	16 Jan 2024	83	17 Dec 2023	30	17 Nov 2023	30
		FB 14a	Footbridge : Segment 1 (Concrete Slab)	24 Apr 2025	24 Apr 2025	23 Feb 2025	60	24 Jan 2025	30	25 Dec 2024	30
		FB 15	Footbridge : Segment 2 (Steelworks Fabrication Drawings)	8 Apr 2024	8 Apr 2024	16 Jan 2024	83	17 Dec 2023	30	17 Nov 2023	30
		FB_15a	Footbridge : Segment 2 (Concrete Slab)	27 Jul 2024	27 Jul 2024	27 Jun 2024	30	28 May 2024	30	28 Apr 2024	30
		FB 16	Footbridge : Segment 3 (Steelworks Fabrication Drawings)	8 Apr 2024	8 Apr 2024	16 Jan 2024	83	17 Dec 2023	30	17 Nov 2023	30
		FB_16a	Footbridge : Segment 3 (Concrete Slab)	27 Jul 2024	27 Jul 2024	27 Jun 2024	30	28 May 2024	30	28 Apr 2024	30
tbridge and		FB 17	Footbridge : Segment 4 (Steelworks Fabrication Drawings)	8 Apr 2024	8 Apr 2024	16 Jan 2024	83	17 Dec 2023	30	17 Nov 2023	30
Pier 2 & 3	BIM Structure (rebar, SEM,	FB_17a	Footbridge : Segment 4 (Concrete Slab)	22 Mar 2025	22 Mar 2025	21 Jan 2025	60	22 Dec 2024	30	22 Nov 2024	30
Pier 2 & 3	Arch, BS)	FB 18	Footbridge: Segment 5 (Steelworks Fabrication Drawings)	8 Apr 2024	8 Apr 2024	16 Jan 2024	83	17 Dec 2023	30	17 Nov 2023	30
		FB_18a	Footbridge : Segment 5 (Concrete Slab)	22 Mar 2025	22 Mar 2025	21 Jan 2025	60	22 Dec 2024	30	22 Nov 2024	30
		FB_19	Footbridge: Segment 6 (Steelworks Fabrication Drawings)	8 Apr 2024	8 Apr 2024	16 Jan 2024	83	17 Dec 2023	30	17 Nov 2023	30
		FB_19a	Footbridge : Segment 6 (Concrete Slab)	22 Mar 2025	22 Mar 2025	21 Jan 2025	60	22 Dec 2024	30	22 Nov 2024	30
	1	FB_20	Footbridge: Segment 7 (Steelworks Fabrication Drawings)	8 Apr 2024	8 Apr 2024	16 Jan 2024	83	17 Dec 2023	30	17 Nov 2023	30
		FB_20a	Footbridge : Segment 7 (Concrete Slab)	22 Mar 2025	22 Mar 2025	21 Jan 2025	60	22 Dec 2024	30	22 Nov 2024	30
		FB_21	Footbridge: Segment 8 (Steelworks Fabrication Drawings)	8 Apr 2024	8 Apr 2024	16 Jan 2024	83	17 Dec 2023	30	17 Nov 2023	30
		FB_21a	Footbridge : Segment 8 (Concrete Slab)	24 Apr 2025	24 Apr 2025	23 Feb 2025	60	24 Jan 2025	30	25 Dec 2024	30
	BIM (BS, ABWF) for internal & external	FB_22	ABWF & BS Works Commencement	10 Aug 2024	10 Aug 2024	12 May 2024	90	12 Apr 2024	30	13 Mar 2024	30
	Amare a 1 d te1	FD 33-	Cl. 341	10 4 2024	10 4 2024	1214 2024	00	13 4 3034	20	12142024	20

# **6.** Project Information Production Methods and Procedures

# **Design Authoring**

Design authoring is a process of developing project information model(s) in accordance with conforming design, the Contractor's design, the scope, and level of information needed for the design elements. The process is summarised as follows:

- Identification of model(s) required for all disciplines
- Identification of content for model creation
- Development of initial model based on conforming design
- Development of project information model from initial model based on detailed

Contractor's design and design development through design review including clash analysis and design change(s) (if applicable)

# **Modelling Strategy**

Scope of Work: Define the scope of work for the project, including the level of detail required for the BIM model, the required deliverables, and the project timeline.

BIM Software and Standards: Select the appropriate BIM software for the project and establish standard procedures for modelling, coordination, and data exchange.

Model Elements: Define the model elements to be included in the BIM model, including the level of detail, accuracy, and completeness required for each element.

Model Coordination and Collaboration: Establish protocols for model coordination and collaboration between all stakeholders, including architects, engineers, contractors, and

BIM Execution Plan Page 15 of 60

subcontractors. This includes defining communication channels, modelling responsibilities, and required meetings.

Quality Control and Assurance: Establish procedures for regular quality control and assurance checks to ensure the BIM model meets the required standards and specifications. This includes defining review processes, identifying responsible parties, and establishing corrective action plans.

Deliverables: Define the required BIM model deliverables, including construction documents, schedules, cost estimates, and other relevant documentation. Establish procedures for reviewing and finalizing these deliverables.

Training and Support: Provide training and support to all stakeholders on the BIM software and modelling procedures. This includes defining training requirements, identifying responsible parties, and establishing training schedules.

# **Model Federation Management**

Description	Discipline	File name
SUW- SUW- SUW-APPROACH LOBBY AT CONCOURSE LEVEL		
30W-AFFROACH LOBBI AT CONCOUNSE LEVEL		
SUW-ARCHITECTURE-PYC	ARC	11286-W-SUW-PYC-ARC-001
SUW-STRUCTURE-OAP	STR	11286-W-SUW-OAP-STR-001
SUW-REBAR-PYC	STR	11286-W-SUW-PYC-STR-020 11286-W-SUW-PYC-STR-021 11286-W-SUW-PYC-STR-022
SUW-FACADE-PYC	FAC	11286-W-SUW-PYC-FAC-001
SUW-SITE-PYC	CIV	11286-W-SUW-PYC-SIT-001
SUW-TEMPORARY WORKS-PYC (e.g., HOARDING)	CIV	11286-W-SUW-PYC-TMP-001
SUW-EXCAVATION & LATERAL SUPPORT-PYC	CIV	11286-W-SUW-PYC-ELS-001

BIM Execution Plan Page 16 of 60

SUW-EXISTING UNDERGROUND UTILITIES-PYC	UUT	11286-W-UUX-PYC-UUT-001				
SUW-DESIGN UNDERGROUND UTILITIES-OAP	UUT	11286-W-UUT-PYC-DRN-001				
SUW-DRAINAGE SREVICE-PYC	MEP	11286-C-SUW-PYC-MEP-001				
SUW-PLUMBING SERVICES-PYC	MEP	11286-C-SUW-PYC-MEP-001				
SUW-DESGIN FOR MANUFCATURE ASSEMBLY - PYC	DfMA	11286-C-SUW-PYC-MEP-001				
SUW-FIRE SERVICES-PYC	MEP	11286-C-SUW-PYC-MEP-003				
SUW-ENVIRONMENTAL CONTROL SYSTEM-PYC	MEP	11286-C-SUW-PYC-MEP-003				
SUW-ELECTRICAL SERVICES-PYC	MEP	11286-C-SUW-PYC-MEP-004				
SUW-STRUCTURAL ELECTRICAL AND MECHANICAL-PYC	MEP	11286-C-SUW-PYC-MEP-004				
SUW-EXTERNAL WORKS-PYC	MEP	11286-C-SUW-PYC-MEP-004				
SUW-COMMUNICATION SYSTEM-PYC	СОМ	11286-C-SUW-PYC-COM-001				
SUW- <b>LIFT &amp; ESCALATORS</b> -PYC	LIF	11286-C-SUW-PYC-LIF-001				
SUW-MAIN CONTROL SYSTEM-PYC	MCS	11286-C-SUW-PYC-MCS-001				
SUW-EXISTING STATION AT SUW CONCOURSE LEVEL						
SUW EXT-EXISTING SYSTEM-PYC	MEP	11286-C-SUW-PYC-MEP-002				

Division of the information models based on volumes, zones and areas shall be additional levels of model breakdown beyond those stated in section 5.1.2 Model Federation Management of this BEP.

BIM Execution Plan Page 17 of 60

Table 5-3- Model Federation Strategy

Discipline	PYC (Full name: Paul Y)	OAP (Full name: ARUP)	Workset
ARC	11286-W-SUW-PYC-ARC-001 (TBA)	11286-W-SUW-OAP-ARC-001(Baselined)	PYC - CLA - Cladding PYC - GLA - Glazing / CWL - Curtain Wall PYC - LOU - Louvres PYC - CEI - Ceillings PYC - RLS - Railings PYC - GRA - Signage
FAC	11286-W-SUW-PYC-FAC-001 (TBA)	11286-W-SUW-OAP-FAC-001(Baselined)	PYC - FAC - Façade
STR	N/A (Non-applicable)	11286-W-SUW-OAP-STR-001 (Action by OAP)	PYC - SFR - Link Bridge PYC - STL - Steel OAP - SFR - Link Bridge OAP - SCO - Concrete OAP - FND - Foundations OAP - STL - Steel
STR	11286-W-SUW-PYC-STR-020 (Action by Xensetech)		PYC - REB - Pier 1
STR	11286-W-SUW-PYC-STR-021 (Action by Xensetech)	11286-W-SUW-OAP-STR-002 (Baselined)	PYC - REB - Pier 2-3
STR	11286-W-SUW-PYC-STR-022 (Action by Xensetech)		PYC - REB - Pier 4
CIV	N/A (Non-applicable)	11286-W-SUW-TMP-SIT-001 (Baselined)	OAP - TMP - Temporary Works
CIV	N/A (Non-applicable)	11286-W-SUW-OAP-ELS-001 (Baselined) 11286-W-SUW-OAP-ELS-002 (Baselined)	OAP - ELS - Excavation & Lateral Support
UUT	11286-W-UUX-PYC-UUT-001 (Action by Xensetech)	11286-W-UUP-OAP-DRN-001 (Action by OAP)	PYC - UUP - Design Underground Utilities OAP - UUP - Design Underground Utilities OAP - UUX - Existing Underground Utilities
MEP	11286-W-SUW-PYC-MEP-001 (Action by REC)		PYC - DRN - Building Services - Drainage Services PYC - PLU - Building Services - Plumbing Services PYC - DfMA - Design for Manufacture and Assembly
MEP	11286-W-SUW-PYC-MEP-003 (Action by REC)	11286-W-SUW-OAP-MEP-001	PYC - ECS - Building Services - Environmental Control System PYC - FSS - Building Services - Fire Services
MEP	11286-W-SUW-PYC-MEP-004 (Action by REC)	(Baselined)	PYC - ELE - Building Services - Electrical Services PYC - SEM - Structural Electrical and Mechanical PYC - C24 - External Works
сом	11286-W-SUW-PYC-COM-001 (Action by REC)		PYC - COM - E&M Systemwide - Communication System
LIF	11286-W-SUW-PYC-LIF-001 (Action by TBA)		PYC - LIF - E&M Systemwide - Lifts & Escalators
MEP	11286-W-SUW-PYC-MEP-002 (Action by REC)	11286-W-SUW-OAP-MEP-002	PYC - EXG - Existing Systems
MCS	11286-W-SUW-PYC-MCS-001 (Action by REC)	N/A (Non-applicable)	PYC - MCS - E&M Systemwide - Main Control System

The contractor has collaborated with the Design Consultant to establish a coordinated model workset and model federation separation in our project's modelling process. This BIM Model federation strategy has been implemented to facilitate multi-disciplinary collaboration throughout the project lifecycle.

	Table 5-4 - Naming Convention for Information Container					
Example Fil	e Name:	: 11286-W-SUW-PYC-ARC-	001.rvt			
Field	Code 8	& Description			Format	
Contract	11286				5 digitals	
Stage	W	= Construction	Z	= As built	1 digital	
Location Code					3 digitals	
Originator					3 digitals	
Subject Code	ARC	= Architecture	STR	= Structural	3 digitals	
	CIV	= Civil	SIT	= Civil - Site		
	LAN	= Architecture - Landscape	Э			
	UUT	= Civil - Underground utilitie	es			
	GEO	= Civil - Geotechnical				
	TMP	= Temporary works				
Unique Number	001	= New design			3-6 digitals	
	002	= Existing				

BIM Execution Plan Page 18 of 60

Once the Federated Model (with LOD 300) is ready for coordination, it will be handed over to the fabricators to input further detailing for design intent. After completion of model detailing, the fabricator will provide BIM Team with the IFC format, such as ABWF model, STR & CIV model, to be integrated into a new Federated Model (with LOD 400).



Naming Convention for Information Container refer to "NAMING STANDARD – March 2023"


# 5.1.3 Volumes, Zones and Areas

Information containers shall be separated into different volumes, zones and areas. The level of breakdown will be subject to the size of the combined information containers in each location / zone / area to avoid ineffective handling due to over-sized model. The optimal size of each subdivision information containers would be approximately 400MB ~ 800MB which is manageable by most computers of 8GB ~ 16GB RAM.

# 5.1.4 Linear Structure Modelling approach

The modelling of linear structures shall be semi-automated by aligning Autodesk Revit and AutoCAD Civil 3D using Dynamo. The brief workflow is illustrated below:

BIM Execution Plan Page 19 of 60




# **7.** Project Information Standards

# **Level of Information Need**

Level of Information Need (LOIN) responsibility matrix is to provide the right level of detail to meet the deliverable requirements for submission. The LOD as shown below is a guideline for the development of the BIM models that will be synchronised in the drawing generation and BIM model coordination for review. The figure 4-1 shows definition of LOIN including Level of Graphics (LOD-G), Level of Information (LOD-I) and Level of Documentation (DOC)

BIM Execution Plan Page 20 of 60





Level of Graphics (LOD-G) Definitions - The level of graphics shall display the correct size and shape from the model elements. Example would be the anchor piles will be modelled at the correct diameter pile size and location.

Level of Information (LOD-I) Definitions - The level of information shall display the correct size and shape from the model elements. Additional information can be added to the model elements to identify the model and to support in the coordination and lifecycle of the project. Adding additional information not required or will not being used should be avoided. Having too much information not being used can slow the performance of the model file which can cause delay which should be removed.

Level of Documentation (DOC) Definitions - There will be no documentation required for design stage which operation and manual documents will be provided at as built stage.

BIM Execution Plan Page 21 of 60





BIM Execution Plan Page 22 of 60

400	Model elements are modelled by discipline or systems which is accurately correct with size, shape, location and orientation. Non graphical information can be added to the model elements.  Additional model elements will be added that will provide information for elements built for construction, example will be manufactures parts used for construction and shop drawings from the BIM model required for fabrication and assembly during construction.	Construction, As-built (Graphics)	
500		As-built (Information)	

BIM Execution Plan Page 23 of 60

# **Project Coordinates and units**

The origin or base point and orientation of the project shall be based on the project location and its reference to the Hong Kong 1980 Grid (HK1980 Grid) and Hong Kong Principal Datum (HKPD). All BIM models shall be coordinated to the project base point, BIM models not coordinated will not be accepted. This will be checked in Navisworks Manage by the BIM Project Manager to ensure the models are coordinated. The BIM Project Manager will notify the BIM coordinators if the model is required to be corrected to the coordinates specified below. This will ensure the models can be geo referenced to any software for the project.

Coordinates	Original Point / Orientation
Easting	837634.028 m
Northing	820725.885 m
Elevation	0 mPD
Rotation angle of the project North to true North	336.516 degrees East

Figure 4-2 - Project Base Point in Revit

Survey Point - Internal

Figure 4-3 Survey Point - Internal in Revit





The Contractor proposes below table of Units

Description	Units	Precision	Example
Length (Civil)	metre	3 decimals	30.150m
Length (All other disciplines)	millimetre	No decimal	24mm
Angle and Slope	Decimal degrees	4 decimals	15.3500°
Area	Square metre	3 decimals	45.350m <sup>2</sup>
Volume	Cubic metre	3 decimals	68.500m <sup>3</sup>
Coordinates system	Easting coordinates in metres	6 digits with 3 decimals	837634.028m
Coordinates system	Northing coordinates in metres	6 digits with 3 decimals	820725.885m


BIM Execution Plan Page 24 of 60

# **Naming Formats**

The naming for the BIM Models are referenced with accordance with the MTR naming standards as detailed in the table below.

The Contractor proposes naming conventions of BIM models as follows:

**Table 4-3 MTR Naming Standard** 



Example: 11286-W-SUW-PYC-STR-001


BIM Execution Plan Page 25 of 60

Table 4-4 File Naming Codes (Example)

Description	Code		
1. Contract	11286		
2. Stage			
Sketch	K		
Statutory Submission	В		
Reference Design / Detailed Design / Pre-Tender	P		
Tender Drawings	Т		
Construction Drawing	W		
As-built Drawing	Z		
3. Location			
4. Originator			
5. Subject			
Architecture (Information Model)	ARC		
Civil (Information Model)	CIV		
Structural (Information Model)	STR		
MEP (Information Model)	MEP		
BIM Execution Plan (Doc)	120		

Remark: Refer to MTR Naming Standard in Associated Documents

4.3.2 The naming for the Assets are referenced with accordance with the MTR naming



Example: TCL-DT-TSY-LAK-PLREJ-82

BIM Execution Plan Page 26 of 60

Table 4-5 Trackside Equipment Naming Codes (Example)

Code
NIL
A11
UUP
000
BMS
DRN
ECS
ELE
ENV
FSS
PLU

Remark: Refer to Naming Standard in Associated Documents

The naming for the Revit files are referenced with accordance with the naming standards as detailed in the table below.

3 REVIT NAMING							
Field No.	1	2	3				
Field Description	ORIGINATOR	_ CATEGORY/TYPE _	DESCRIPTION				
Examples:							
Revit Family		_ LIF _	landingdoor-BOH-A				
Parametric Definition		_ Dyn4Revit _	equipment2excel				
Levels		_ FFL _	absolute				
Views		_ elevation	east				
Schedules		_ framing _	concourse-steel				
Basic Walls		_ wall	lbwext-PLA50-RCC100-PLA25				
Stacked Walls		_ wall	ext-PLA-RCC150-GLS150				
Curtain Walls		_ wall	P1500x500-M50x150				

Example: PYC-LIF-landingfoor-BOM-A

BIM Execution Plan Page 27 of 60

The naming for the Civil files/object are referenced with accordance with the naming standards as detailed in the table below.

# 4 CIVIL NAMING

# 4.1 Alignment File naming

Field No.	1		2		3		4		5
Field Description	CONTRACT	-	ORIGINATOR	-	STAGE	-	PROJECT	-	REVISION
Examples:						•			
ALG file	01234			-	Р	_	WIL	_	01
ALG file Examp	01234 ble: 11286-	-	P-WIL-01	-1	Р	-	WIL	-	01

# 4.2 Alignment object naming

Field No.	1		2		3		4
Field Description	ORIGINATOR	-	SYSTEM	-	DESCRIPTION	-	PURPOSE
Examples:							
Alignment Object 1		-	PWY	-	UP_01_V01	-	20
Alignment Object 2			PWY		UP01_V03		20
Alignment Object 3			PWY		XADM01_V03		20

Example: PWY- UP 01 V01-20

Remark: Refer to Naming Standard in Associated Documents

4.3.5 The naming for the Object and Parameter are referenced with accordance with the naming standards as detailed in the table below.

5.4	Object file naming
5.4.1	Object file naming field

Field No.	1		2		3		4
Field Description	ORIGINATOR	-	SYSTEM	-	DESCRIPTION	-	PURPOSE
Examples:							
Object 1		-	AFC	-	GateArray	-	30
Object 2		-	BP	-	Baseplate	-	20
Object 3	OAP	-	POW	-	PLC_Panel	-	20
Object 4	WSP		SIG	-	TracksideBeacon	-	30
Object 5		-	POW	-	SF6_GasLeakageAlarmPanel	-	20
Object 6	OAP		PWY	-	DTM_kowtkt01	-	20

Example: AFC- GateArray-30

BIM Execution Plan Page 28 of 60

Description	Code
1. Originator	
2. System	
Building Services –Building Management System	BMS
Building Services – Drainage Services	DRN
Building Services –Environmental Control System	ECS
Building Services -Electrical Services	ELE
Building Services -Environmental	ENV
Building Services –Fire Services	FSS
Building Services –Plumbing Services	PLU
3. Description	
110V_EquipmentSpecificTextDescription	110V with Equipment Specific Text Description
APG_FixedPanel	Automatic Platform Gate - Fixed Panel
4. Purpose	
10	Placeholder
20	Detailed
30	Manufacturer
40	Operations
50	Presentation

Remark: Refer to Naming Standard in Associated Documents


BIM Execution Plan Page 29 of 60

# 4.4 Digital objects

Digital objects (e.g. Revit families, Civil3D objects) are among the fundamental components of any Information Model. They contain 3D and 2D Information as well as non-graphical Attributes of real-life elements used in design. As such digital objects form an important part of Project Deliverables and is prepared by the Contractor according to the following requirements:

- The Contractor creates digital objects by using Client's respective BIM Object Templates.
- 2. Please refer to Contractor's CDE for BIM Object Templates as follow path:

Figure 4-4 BIM Object Templates for drawing production – CDE Path "02. SHARE → 2.2 BIM → 2.2.1 Title Block"



- The Contractor creates digital objects are parametric as fat as necessary and practicable.
- The Contractor creates digital objects assigned to related family categories and classification.
- 5. English shall be used in developing digital objects.

BIM Execution Plan Page 30 of 60

# 4.5 Asset Information Requirements

#### 4.5.1 Asset Classification

All assets within the project must be classified according to a standardized system, such as the Uniclass 2015 classification system, to ensure consistency and accuracy in the management and maintenance of assets.

#### 4.5.2 Asset IDGGGG

Each asset must be assigned a unique identifier, such as an Asset ID, that can be used to track and manage the asset throughout its lifecycle.

# 4.5.3 Equipment Number

All equipment within the project must be assigned an equipment number or other unique identifier, to enable tracking and maintenance of equipment throughout its lifecycle.

#### 4.5.4 Data Structure

Asset information must be structured in a consistent and standardized format, to enable efficient management and maintenance of assets. The format must be agreed upon by all project stakeholders and documented in the BIM Execution Plan.

#### 4.5.5 Data Delivery

All asset information must be delivered in a specified format, such as a CSV file or Excel spreadsheet which can be compatible with the project's BIM software and asset management system.

# 4.5.6 Validation and Integration

Asset information must be validated and integrated into the project's BIM model or asset management system, using appropriate tools (e.g. COBie) and processes to verify and validate built items with point cloud data in synchrony with the progress of construction.

#### 4.5.7 Review and Update

The asset information must be reviewed and updated throughout the project lifecycle, to ensure that it remains accurate and up-to-date. It must be included processes for reviewing and updating asset information, as well as identifying and resolving any discrepancies or issues that arise.

BIM Execution Plan Page 31 of 60

# 4.5.8 Asset Information Management Workflow (From PIM to AIM)

1) The main contractor provides a spreadsheet to the sub-contractor with a list of required asset information, including asset classification, asset ID, equipment number, and any other relevant data fields. Parameter naming referenced with accordance with the naming standards as "Section 4.3 Naming Formats"

# Specific Structured Information Requirements

The following is to be read in conjunction with the GS and PS for Information Modelling.

param_name_concat	id_param	param_general_description
MTR-ASSET-1_1_ID_EquipNo	P0012	Asset-ID-EquipmentNo
MTR-ASSET-	P0013	Asset_ID_(Description)
1_2_ID_EquipDescription		
MTR-ASSET-1 3 ID ParentEquipNo	P0014	Asset ID (Parent Equipment No)
MTR-ASSET-	P0015	Asset_ID_(Parent_Equipment_Description)
1 4 ID ParentEquipDescription		
MTR-ASSET-2_1_EquipClass	P0016	Asset Classification (Equipment Class Description)
MTR-ASSET-2_2_EquipHeirarchy	P0017	Asset_Classification_(Equipment_Hierarchy)
MTR-ASSET-	P0018	OEM_info_(Manufacturer)
3_1_OEM_Manufacturer		
MTR-ASSET-3_2_OEM_Model	P0019	OEM_info_(Model)
MTR-ASSET-3 3 OEM SerialNo	P0020	OEM info (Serial No)
MTR-ASSET-4_1_Quantity	P0021	Quantity
MTR-ASSET-4_2_UoM	P0022	Unit of Measure
MTR-ASSET-5 1 LocLineServed	P0023	Location (Line Served)
MTR-ASSET-5 2 LocDirection	P0024	Location_(Direction)
MTR-ASSET-5_3_LocFrom	P0025	Location_(From_Location)
MTR-ASSET-5 4 LocTo	P0026	Location (To Location)
MTR-ASSET-5_5_LocChainageFrom	P0027	Location_(Chainage_From)
MTR-ASSET-5 6 LocChainageTo	P0028	Location (Chainage To)
MTR-ASSET-	P0029	Life_Cycle_(Date_Placed_in_Service)
6_1_LC_PlacedInService		
MTR-ASSET-6_2_LC_HandoverDate	P0030	Life_Cycle_(Handover_Date)
MTR-ASSET-7 1 MaintContractNo	P0031	Maintenance Contract No
MTR-ASSET-7_2_MaintContractor	P0032	Maintenance_Contractor
MTR-ASSET-7_3_WarrantyFrom	P0033	Warranty_from
MTR-ASSET-7 4 WarrantyTo	P0034	Warranty_to
MTR-ASSET-8 1 FAR No	P0035	Fixed Asset Register Number

Figure 8 - Example of Spreadsheet with required asset information

- The sub-contractor inputs the required asset information into spreadsheet, using the format and structure that in compliance with Specific Structured Information Requirements.
- The sub-contractor provides the required asset information to the main contractor in a specified format, such as a CSV file or Excel spreadsheet.

BIM Execution Plan Page 32 of 60

- 4) The main contractor reviews the information provided by the sub-contractor to ensure fulfilling the project's information requirements and the data is accurate and complete.
- 5) The main contractor integrates the information provided by the sub-contractor into the project's BIM model or asset management system, using the appropriate tools (e.g. Revit) and processes to ensure that the data consistency and accuracy.
- 6) If any issues or discrepancies are identified during the validation or integration process, the main contractor communicates with the sub-contractor to resolve them and make sure that the information is correctly input.
- Finally, the main contractor reviews and updates the information throughout the project lifecycle and complete Asset Information Management (AIM) Workflow.

# 8. Software, Hardware, IT Infrastructure and Training

# Software Platforms

The following BIM software platforms will be used across the project team for all deliverables:

The models will be converted to 2022 version once all models have been established. The upgrade to 2022 will be done in ACC (Formerly known as BIM 360) Revit Cloud Model Upgrade.




Figure 6-1 ACC Document Management - Revit Cloud Model Upgrade

The following BIM software platforms will be used across the project team for all submissions.

BIM Execution Plan Page 33 of 60

No	Function / form	Originating application	Version
1.	Information Model Submissions	Autodesk Navisworks Manage / original authoring platform	2022
2.	Design authoring of buildings and other vertical facilities	Autodesk Revit (Architecture, Structure, MEP)	2022
3.	Design authoring of civil and other linear facilities	Autodesk Civil 3D	2022
4.	Alignment design	N/S	N/S
5.	Federation, coordination and design review	Autodesk Navisworks Manage / Autodesk Construction Cloud (Formerly known as BIM 360)	2022
6.	Construction planning, sequencing and simulation	Synchro	2022
7.	Presentation of 4D animations, videos, analyses, etc.	Synchro	2022

8.	Drawings	Autodesk Revit	2022
9.	Drawings	Autodesk Civil 3D	2022
10.	Clash Analysis reports	Autodesk Navisworks Manage	2022
11.	Schedules, Tables	N/S	Latest version
12.	Document production	MS Office (Word, PowerPoint, Excel, etc.)	Latest version
13.	Document reviewing and commenting	MS Office (Word, PowerPoint, Excel, etc.)	Latest version
14.	Images	.jpg, .png	Latest version

BIM Execution Plan Page 34 of 60

#### **Submission File Formats**

Project deliverables will be submitted in the following file formats:

Table 6-2 Submission file Formats

Function	File Format	Notes
Native Model File	.rvt .dwg	Primary design development
Information and Coordination Model File	.nwc .nwd	Design review
Model Federation	.nwf .nwd	Design review
Clash Report	.nwf .nwd .pdf .xls	Navisworks Manage
Schedules, Tables	.xls .xml	Wherever possible generated directly from the native model
Drawings	.dwg .pdf	2D representations generated directly from the native model. (PDF only in specific justified cases)
Reports	.pdf	From native doc, xlsx using data from PIM
Images	.jpg .png	
Construction Planning, Sequencing and Simulation	.nwd .sp	Graphical (3D) and 4D design information
4D Simulations, Animations, Videos	.mpg .avi	Or other agreed and approved format

# Information Modelling Capability Assessments and Training

The project BIM Manager and discipline BIM coordinators shall ensure the modelling capability for the team have the skills to deliver in BIM. The team should have experience from previous BIM projects or the understanding of using Revit, ACC (Formerly known as BIM 360) and Navisworks Manage.

The Contractor, sub-contractor, BIM sub-consultant will complete the Supply Chain Capability Summary (SCCS) forms based on assessments of their project delivery team's capability to manage and produce BIM-related information and availability of information technology (IT) to demonstrate their capacity of meeting the requirements of the **MTRC** scope.

# **Training Methodology**

BIM Execution Plan Page 35 of 60

BIM training, which will be provided by qualified project staff, in the following areas is proposed to enhance the project team's capabilities in BIM utilization:

- BIM fundamentals
- BIM project implementation
- CDE and Data management
- Hands-on software training in model navigation, 4D simulation, clash analysis, generation of schedules and tables, drawing production etc.

Training will be scheduled in conjunction with the programme so that staff development in BIM processes is maintained throughout the critical parts of the project. Workstations with necessary software installed will be provided by the Contractor to the training attendees for software training, which can be carried out via video conference or at the training venue set up by the Contractor to meet the needs of the project team.

Training / workshop	Description	Trainer	Audience	Frequency
Training of design review software	Participates will learn how to navigate, sectioning and measure the models	Contractor BIM Coordinator (MCBC)	Project team	Upon contract commencement and hold bi- monthly to support newcomer of the projects
Training of CDE platform (BIM Viewer)	Participates will learn how to review documents, mark up and make comments on the drawings	Contractor BIM Coordinator (MCBC)	Project team	Upon contract commencement and hold bi- monthly to support newcomer of the projects
Training of CDE platform  (Document Management)	Participates will learn the standard, rules and naming convention of information container, the workflow of information exchange and submit and approval	Contractor BIM Manager (MCBM)	Document controller	Upon contract commencement and hold bi- monthly to support newcomer of the projects
Training of 4D simulation software	Participates will learn how to review 4D models	Contractor BIM Coordinator (MCBC)	Programme planner	Upon contract commencement

BIM Execution Plan Page 36 of 60


The BIM Project Manager shall have a BIM Kick-off meeting to brief the team of the setup of the BIM project. Training shall be provided for team members that need support in areas they do not have the skill level to deliver in BIM. The training will be recorded on Teams which the training will be on the project training. On the project training will ensure the training is specific to meet MTR BIM requirements and submission.

Training/ Workshop	Description	Trainer	Audience	Frequency
BIM Kick-off Meeting	Briefing on the setup of the BIM project and MTR standards and requirements	Project BIM Manager	Members from each discipline	Start of the project
Teams BIM Training	Troubleshooting training in providing solutions and workflows to deliver BIM	Project BIM Manager	Discipline teams	Upon request

BIM Execution Plan Page 37 of 60

## 9. BIM Team Resources, Competency and Training

#### 3.3 Organisation Chart



BIM Execution Plan Page 38 of 60

# 3.4 Organisational Roles and Responsibilities

# The organisational team roles are:

Table 3-1 Organisational Roles and Responsibilities

Role & Trade		Organisation	Responsibilities
Client		MTR Corporation	Scope of Service, EIR, CDE
Mair	n Contractor	Paul Y.	Lead Construction, Overall Project Delivery Management
	Architecture		
Design Team	Structure & Civil	ABUB	Arch and Structural design
Design Team	Underground Utilities	ARUP	models shall be authored by ARUP.
	Temporary Works		
BIM I	BIM Management		Overall BIM Management of both Design Team & Construction Team for MTR Existing SUW Concourse to Footbridge.
	STR - Steelworks Fabrication	KPa	Modeling based on Steelworks Fabrication design details drawings.
	ABWF - Cladding	TBA	
	ABWF - Glazing / Curtain Wall	ТВА	
	ABWF - Louvres / Windows	ТВА	
	ABWF - Ceiling	TBA	
	ABWF - Metal Work	TBA	
Construction	ABWF - Signage	TBA	
Task Teams	ABWF - Façade	TBA	
	Rebar Modelling	XenseTech	Modeling based on rebar design details drawings.
	Temp Works	TBA	
	Proposed ELS	Mannings	Modeling based on Proposed ELS design details drawings.
	Existing Underground Utilities Modelling	XenseTech	Modeling based on UU record drawings, UU survey reports, trial pits.

BIM Execution Plan Page 39 of 60

E&M - Building Services	REC	Environmental Control System, Drainage Services, Plumbing Services, Electrical Services, Fire Services, Lift & Escalator, Communications System, SEM, CBWD modeling
E&M - COM System	REC	COM Equipment (e.g. CCTVs / Speakers) modeling
E&M - Main Control System	REC	Main Control System Equipment modeling
E&M – Lift & Escalator	TKE	Lifts, Escalators & Moving Walkways
4D Modelling	XenseTech	4D Initial Modeling based on Accepted Programme. 4D Progress Modeling based on Monthly Programme Update.

# 3.5 Information Management Roles and Responsibilities

## 3.5.1 The information management team roles are:

Table 3-2 Information management Roles and Responsibilities

1	Table of Information Management Roles and Responsibility			
Discipline	Role	Responsibility		
Client	Project Information Manager (PjIM)	Manage and monitor the compliance of data structure, collaborative working environment and deliverables submitted by the Contractor against the BEP.		
Client	Project Information Engineer	Assist the PjIM in reviewing Information models and assisting with the management of CDE workflows.		
Main Contractor	Contractor's Project Manager (CPM)	Lead and drive the BIM adoption among construction team     Manage and monitor the BIM implementation, to ensure BIM can achieve client's value.		
Main Contractor	Contractor's BIM Manager (CBM)	Develop BIM quality assurance/quality control framework.     Consolidate and propose BIM hardware and software provisions, and propose digital technologies suitable for 11286. Establish BIM staffing requirements and BIM modelling		

BIM Execution Plan Page 40 of 60

Та	Table of Information Management Roles and Responsibility			
Discipline	Role	Responsibility		
		strategy / protocol. Resolve BIM implementation issues. Establish soft landing strategies for information model handover, operation training and project close out.  Management Assess the BIM resources requirements, organize and coordinate the resources of the BIM team for the project. Monitor, manage and report the time, cost, and quality performance of BIM implementation in the project. Manage federated models verify versions and quality.  Implementation Work with the project teams to develop and implement BIM technologies, BIM Execution Plans, workflows and processes, enforcement, and quality audits. Lead the BIM implementation in the projects to meet the objectives of the projects. Oversee the quality and timely delivery of the BIM deliverables in the projects, maintain a clear and up-to-date register, and ensure and sign off the quality of the deliverables. Lead BIM-related coordination workshops and monthly progress meetings and maintain records of attendance and decisions made. Lead the BIM teams to ensure that the execution of BIM in projects complies with the relevant BIM standards and project specifications and requirements. Help DDC to successful implement the BIM strategy.  Training Lead the BIM training in the project and assess and certify the project team competence prior to allowing them to carry the relevant items of BIM work.		
Main Contractor	Contractor's BIM Coordinator (CBC)	Supervise the work of BIM modelers in BIM implementation     Supervise the production and revision of BIM models and maintain the BIM dataset for various BIM Uses/applications in accordance with the relevant BIM Execution Plan, BIM standards and project specifications.     Oversee the project schedule, quality, and manpower arrangement for the project.		

BIM Execution Plan Page 41 of 60

Та	Table of Information Management Roles and Responsibility			
Discipline	Role	Responsibility		
		<ul> <li>Coordinate and assist in BIM implementation and ensure all project BIM deliverables comply with the relevant BIM standards and project specifications and requirements.</li> <li>Assist the BIM Manager in BIM-related reporting or meetings.</li> <li>Coordination</li> <li>Assist and support the BIM Manager in BIM collaboration and coordination with the Employer, consultants, contractor, subcontractors, suppliers, and others in construction team to meet the objectives of the project.</li> <li>Communicate and coordinate with different external project stakeholders in the various disciplines, including architects, engineers, surveyors, and the operation team to maximize the utilization of BIM.</li> <li>Training</li> <li>Provide training at project and team level.</li> <li>Prepare training materials, videos, user manual, etc.</li> </ul>		
Main Contractor	BIM Modeler	<ul> <li>Author/Create, modify, and maintain BIM models, BIM objects and BIM datasets to meet the relevant BIM standards, BIM uses/applications, project specifications and the requirements provided by the design and/or construction professionals.</li> <li>Attend and assist the professionals in the relevant disciplines in their work in BIM project coordination meetings.</li> <li>Produce project drawings/plans and schedules from BIM models for approvals or statutory submissions.</li> <li>Provide support to the BIM manager(s), BIM coordinator(s) and design and/or construction professional(s) in BIM implementation in projects.</li> </ul>		
Main Contractor	MEP Engineer, Civil Engineer, Building Engineer	Review BIM models and provide necessary information for BIM uses. Coordinate clash and issue found in 3D coordination, clash detection and issue management. Utilize information model for engineering calculation, design quality, buildability and operation performance review.		

BIM Execution Plan Page 42 of 60

Table of Information Management Roles and Responsibility			
Discipline	Role	Responsibility	
Main Contractor	Quantity Surveyor (QS)	Review BIM models and provide necessary information for BIM uses.     Extract the quantities from the model	
Main Contractor	Safety officer (SO)	Review BIM models and provide necessary information for BIM uses. Review 4D information and Construction Sequence Simulations for risks assessment to eliminate hazards / mitigate risks, improving safety performance.	
Main Contractor	Surveying Team (SY) & Environmental Office (EO) & Quality Management Team (QM)	Digital Survey Team provide 3D scans point clouds / mesh models, photogrammetry models, coordinates and alignment.     Review BIM models and provide necessary information for BIM uses.	
Design Teams, Subcontractors	Task Information Managers	Production of design outputs related to a discipline specific, package based or time-based task     Produce Task Information Delivery Plan (TIDP).  Management     Direct corresponding Task Teams compliance with BIM standards and methods.  Implementation     Execute TIDP to ensure timely delivery of the BIM deliverables for coordination     Align the production of task Information using agreed systems     Authoring the production of task Information is suitable within common data environment (CDE).     Issue approved information within the common data environment  Training     Provide training at task team level.     Prepare training materials, videos, user manual, etc.	
Design Teams, Subcontractors	BIM Authors	Implementation  • Author/Create, modify, and maintain BIM models, BIM objects and BIM datasets to meet the relevant BIM standards, BIM	

BIM Execution Plan Page 43 of 60

Table of Information Management Roles and Responsibility			
Discipline Role Responsibility			
		uses/applications, project specifications and the requirements provided by the design and/or construction professionals.  • Attend and assist the professionals in the relevant disciplines in their work in BIM project coordination meetings.  • Produce project drawings/plans and schedules from BIM models for approvals or statutory submissions.  Provide support to the BIM manager(s), BIM coordinator(s) and design and/or construction professional(s) in BIM implementation in projects.	

# **Project Team Chart**

Please refer to" 1.7.3 Submission of Contractor's Organisation Chart and Schedule of Personnel" - <a href="https://doi.org/10.1016/j.com/10.10

BIM Execution Plan Page 44 of 60

# 10. Quality Assurance

Table 5.24-1 BIM Quality Control Checklist

Definition	Responsible Party	Software Program	Frequency	Checked
Single Discipline Check	Discipline	Model/Drawing reviews	Issue to Shared, published data	
Inter Disciplinary Check	All Disciplines	Model/Drawing reviews	Published data	

#### Table 5.24-2 BIM Model Validation Checklist

Level of Check	Action	Software	Checked
Issue for Coordination	BIM Checklist sign off by discipline coordinator	Autodesk Model Review, manual checks	

### Table 5.24-3 BIM Checklist

Item	Checked
CAD standard check (compliance with agreed CAD standards)	
Models at the correct Origin and Orientation of project base point	
Models must be at 1:1 Scale, that is, no dimensions changed without changing the underlying model geometry	
2D linework must be aligned to its associated 3D surface at correct orientation, elevation and origin	

BIM Execution Plan Page 45 of 60

There must be no duplicate objects	
There shall be no 'custom' objects, that is, objects created by the user that are not approved or part of the Originators and/or Project library	
Models must be stand-alone project files with all linked data bound or removed	
All 'hidden', 'scrap', 'temporary' or redundant objects / geometry / linework must be deleted	
All author created views, sheet layout data (title blocks, annotation etc) and templates must be removed with the exception of the "model title view"	
All data not authored by the originator must be removed (e.g. shared grid file linked into architectural model)	
Model integrity must be correct (e.g. columns meet beams and slabs - no gaps)	
All objects must have the extended properties completed against the required Level of Detail	
All object properties must be spelt and formatted correctly and consistently	
All model files must have the correct filename and metadata	
Check that the model is using the current shared parameters, and keynotes files	

Checks	Definitions	Responsible Parties	Methodologies	Frequency
LOD-G Proposed	Ensure the geometry of the object elements are modelled to	BIM Coordinators	Visual check of 3% of modelled objects	Bi-Monthly
	the proposed	BIM Project Manager	Visual check of 5% of modelled objects	Before the major submission stage of the deliverables
LOD-I Proposed	Ensure the attributes of the object elements are created/entered to	BIM Coordinators	Visual check of 3% of modelled objects using exported table	Bi-Monthly
	the proposed format and contents	BIM Project Manager	Visual check of 5% of modelled objects using exported table	Before the major submission stage of the deliverables
Geometrical accuracy and engineering standard compliance	Ensure the objects are modelled to the exact size, location and orientation	BIM Coordinators	Overlay of design drawings, and random annotation of XYZ positions.	Bi-Monthly
compliance	according to the LoD-G proposed.	BIM Coordinators	Random check on design dimension and engineering requirements	Before the major submission stage of the deliverables

BIM Execution Plan Page 46 of 60

Naming Convention	Ensure the file name, non-system object names follow the proposed standard	BIM Coordinators	Visual Check	Monthly
File format	Ensure the BIM models are created with the proposed file format and version	BIM Coordinators	Random file checks	Monthly
Modelling Methodologies	Ensure the BIM objects are created with the proposed	BIM Coordinators	Visual check of 3% of modelled objects	Bi-Monthly
	modelling methodologies	BIM Project Manager	Visual check of 5% of modelled objects using exported table	Before the major submission stage of the deliverables
Project Basepoints	Ensure the reference point of each model comply	BIM Project Manager	Visual check of project basepoints	First week after the model file is created

BIM Execution Plan Page 47 of 60

#### 3.7 Client's Common Data Environment

- 3.7.1 All production and handover Information, including both graphical and non-graphical model Data, are managed through the Client's CDE. The Client's CDE acts as the central storage of Project Information, allowing the latest up to date Information Shared with the whole Project Team and all other Project stakeholders and used by Project Team members in a collaborative decision-making process. The Client establishes and maintains the Client's CDE in line with BS EN ISO 19650-2:2018.
- 3.7.2 The Project Manager arranges for the Contractor to have reasonable access to the information in the CDE Solution and Workflow as provided. The Contractor follows the digital project review process directed by the Project Manager and is responsible for training its staff accordingly.
- 3.7.3 The Contractor proposes the Information workflow and user access within Client's CDE as follows:

Design
Cornsultant

Main
Corntractor

Macroafech
RBM Manaparrent
RBM M

Figure 3 3 Workflow of Common Data Environment (CDE)

BIM Execution Plan

Page 48 of 60

The Contractor shall submit all deliverables which is for review, authorize or accept into Client Shared. A workflow shall be initiated from Client shared to Client Published. The Contractor has view access in Client Published to be informed for any approved information.

### 3.7.4 "ACC Bridge" Function

The Bridge function start from a single CDE to other single CDE by bridge process, whenever the folder is updated and then the linked folder/s will be updated together. The automatic does not include selected files, any subfolders, or files inside subfolders.

Figure 3-4 Example of Bridge Function - From CDE 1 to CDE 2



#### 3.8 Contractor's Common Data Environment

- 3.8.1 The Contractors CDE will be hosted in ACC (Formerly Known as BIM 360) platform. All discipline shall be working in the CDE for collaboration and to receive the latest models shared.
- 3.8.2 01-WIP folder shall be the native file folder location for all disciplines to develop the models and drawings
- 3.8.3 02-Shared folder shall be the native files, copied out for sharing for other disciplines to consume and link to their native models.
- 3.8.4 **03-Publish** folder shall be the files shared for review and coordination.
- 3.8.5 **04-Archive** folder shall be proactive archiving for current, inactive or superseded Information.

The Contractor provides, own and manage the contractor's CDE in line with BS EN ISO 19650-2:2018.

All deliverables shall be started in Contractor WIP. Client has upload access in the folder to issue information to Contractor if any. After the information is ready for coordination, task team leader shall upgrade the information from Contractor WIP to Contractor Shared. Client has view download and upload access in Contractor Shared to make advance comments into the information if any. While the information is ready for submission, contractor's project manager or the presentative shall submit the information into Client Shared. For those history of information shall be coped into Contractor Archive, client has view access into the folder during project period for audit trial.

BIM Execution Plan Page 49 of 60


The Contractor proposes the Information workflow and user access within Contractor's CDE as follows:

Contractor Client CDE CDE Client Shared Contractor WIP Non-Verified design Information (Information Model Comprising 3D Model, Drawings, Documentation, Programs and Review, Authorize or Accept Any Other Production Contractor view, download and upload only Information) used by Contractor only; " Client upload only Authorized Contractor Shared Client Published Shared resources VERIFIED Design Information (Information Production Information Suitable for Procurement, Construction, Maintenance Complete, Model) Shared with the Project Audit Trail Team; Ongoing Design VERIFIED & VALIDATED Development Authorized \* Client view, download and \* Contractor view only upload only Contractor Archive JOURNAL History (Audit Trail) Maintained for Knowledge, Regulatory and Legal Requirements. \*Client view only

Figure 3-5 Workflow of Common Data Environment (CDE)

BIM Execution Plan Page 50 of 60

Figure 3-6 Coordination environment among contractor and designer



To avoid dutiplate information may be produced by the above workflow and make information management become effective, naming convention of metadata shall be proposed. The Contractor propose the metadata according to ISO19650-2:2018 as follows:

	Table 1 – Table of Metada	ta for Information Container
For all informat	ion container in CDE	
Metadata	Example	Remarks
File name	Name	Refer to (4.3 Naming Format)
Version	V1	Automated generated by ACC
Mark-up	Y/N	Automated generated by ACC
Issue	Y/N	Automated generated by ACC
Last updated	Apr 26, 2022 11:06 AM	Automated generated by ACC
Updated by	Johnny Tam	Automated generated by ACC
Status Code	S1	Refer to table of status code

A standardized status code shall be adopted to differentiate information container. The status code shall be assigned by task team leader. Different status code represents the purpose or intention of the information container.

	Table 2 – Ta	ble of status code	
Code	Description	Revision	
Work in p	rogress (WIP)	'	

BIM Execution Plan Page 51 of 60

tatus	Preliminary revision and version
ual)	
e for coordination	Preliminary revision
e for information	Preliminary revision
e for review and comment	Preliminary revision
e for stage approval	Preliminary revision
awn*	N/A
e for PIM authorization	Preliminary revision
e for AIM authorization	Preliminary revision
l)	
zed and accepted	Contractual revision
sign-off (with comments)	Preliminary revision
ceptance)	
structed record document	Contractual revision
	e for coordination e for information e for review and comment e for stage approval awn* e for PIM authorization e for AIM authorization il) ized and accepted sign-off (with comments) ceptance) structed record document

	Table 3 – Table of application of status code
S0	Assigned by task teams to identify information containers as Work in Progress and not yet suitable to be Shared outside the task team.
S1	Assigned by task teams to limit the information container's use to coordination activities only by its recipients. Information containers assigned this status should only be used to qstand or advance their own deliverables in a coordinated manner. It is likely to be assigned to a geometrical information container, but it is important to understand that S1 can be assigned to any information container.
S2	Assigned by task teams to limit the information container's use for any specific activity by its recipients. This status denotes that the author is providing it for information only to help others in certain situations. For example, reference information provided by the appointing party such as a dilapidations report would be given this status code. Another example would be an email file containing site photos.
S3	Assigned by task teams to limit the information container's use to commenting and review activities only by its recipients. Information containers assigned this status should only be used to review their contents against the information requirements or to provide feedback on their development.  For example, an outline proposal to solve a technical design problem during Concept
S4	stage.  Assigned by task teams to limit the information container's use to stage approval activities only by its recipients. The outcome of the review following this status should be the acceptance of the information container that it meets stage requirements.
S5	This status code is not used in the National Annex
S6	Assigned by task teams to limit the information container's use to the lead appointed party's authorization of the project information model (see ISO 19650-2 clauses 5.7.1 and 5.7.2). The information should not be used for contractual purposes, for example, construction until the project information model that it forms part of has been authorized by the lead appointed party and accepted by the appointing party. If the project information model is rejected but the information container itself does not require amendment its status will remain at S6 until the project information model is

BIM Execution Plan Page 52 of 60

	authorized. If the project information model is rejected and the information container requires amendment, then it is assigned the S0 status until it can be shared again. Note that a project information model could be a single information container, or it could be multiple information containers depending on the exchange information requirements.
S7	Assigned by task teams to limit the information container's use to authorization activities for Stage 6 (Handover) only by its recipients. The outcome of this status should be the authorization of the information model that it meets the requirements for handover to facilities and asset management teams.
A1, An, etc.	Assigned by task teams to represent the Stage the authorized and accepted information container relates to in accordance with the task information delivery plan. For example A1 would represent an authorized and accepted information container generated in Stage 1, A2 would represent Stage 2 and so on
CR	Assigned by task teams to represent an information container that has been authorized and accepted and was previously assigned an S7 status.

### **11.** Handover Procedures

#### Handover Review Strategy

To ensure that all Project Close-out Checklist items are completed prior to handover to the end-user, the following review strategy will be implemented:

Before Project Close-out (At least 1-Month): A review of the Project Close-out Checklist items will be submitted to ensure that all items are on track for completion. Any items that require additional attention will be identified and addressed promptly.

Before Project Close-out (At least 3-Months): A more comprehensive review of the Project Close-out Checklist items will be submitted to ensure that all items are progressing as planned. Any items that are falling behind schedule will be identified, and corrective action will be taken to bring them back on track.

BIM Execution Plan Page 53 of 60

# Appendix A – Master Information Delivery Plan (MIDP)

	DELIVERABLE PRODUCTION SCHEDULE			Constructor's Sub	mission Sched	ule									
-		Contract No:	1	PYCs Representative:	-										
					ation details	1									
10	NAME	STRUCTURE OF INFORMATION	CLASSIFICATION CODE	FORM	FORMAT	DESCRIPTION	CONTENT COMMENTS	Target Submission	Target Submission	Target Approval Date	REFERENCE	TARGET	APPROVAL	SUBMITTING	Programm
ID of project stage, group if deliverables, deliverable or information container (IC), i.e. file)	(of project stage, group of deliverables, deliverable or information container (IC) f file)	(structured - can be interpreted by a machine unstructured - must be interpreted by a human)	(Uniclases 2015)	(form of presenting information based on Uniclass 2015)	(Ne format)	(plain tenguage)	(specific requirements for the contents)	PYC to MTR	Date To STA		(template or other reference to be used to prepare information)	SUBMISSION MLESTONE (weeks after appointment starting date)	MILESTONE (weeks after submission milestone)	(Contractor / Subcontractor)	
.1.1	Selvy 6 Holds														
0.1.1.1	Submission of Site Personnel Uniform Design	Unstructured	PM 60 70 95	FI BD	adf	Management Plan									
0.1.1.2	Submission of Uniform Changing Facilities	Unstructured	P54_60_70_95	FLSE	pff	Management Plan									
0.1.13	Submission of Safety and Health Management Plan	Unstructured	PM 60-70-17	FL80	adf	Management Plan									_
0.1.14	Submission of Emergency Action Plan	Unstructured	PM 80 50 30	ri 80	adf	Management Plan	_						_	_	-
0.1.15	Submission of Air Quality Management Plan (AQMP) Submission of Health & Safety Plan	Undrustured	PM 60 70 95 PM 60 70 17	F1 60	.00°	Management Plan Management Plan		104623		3-bar-23			_	_	11200-40
0.1.1.7	Welfary and Higginse Plan	Unductured	PM_60_70_17	0.60	adf	Management Plan		1112-75		10471					11,710-90
0.1.18	Submission of Emergency Plan for Kind Colleges	Systructured		FL 80	all	Management Plan									_
0.1.19	Submission of Energency Plan for Ground Settlement and Collapse	Systematured		f1.80	adl	Management Plan									
0.1.110	Submission of Onio Management Flori	Unstructured	PSI 60 70 27	ri 80	.adf	Management Plan									
0.1.1.11	Report for Drill in relation to fire occur at Temperary Site Office	Unstructured	PM 60-70-17	F1 80	.edf	Management Plan									
13	Quilty														_
0.12.1	Submission of Cuality Plan Submission of Contractor's Submission Schedule	Unitroduced Unitroduced	PM 30-20-89	0.60	ad!	Management Plan Management Plan									-
0.13.2	Submission of Survey Quality Ran	Unstructured	PM 10 20 68	0.66	38°	Management Plan	_								-
0.12.4	Submission of proposed action plans for CQA 11286 ES	Undistried	PM 10 20 69	F1 80	all all	Management Plan									_
0.125	Action consistion record for Contractor Guidty-Audit (CGA 11286-01)	Westructured	PM 30 20 69	ri se	eff	Management Plan									
0.12.6	Submission of Internal Audit Report PSASS	Unstructured	PM 30 20 69	ri 80	.edf	Management Plan									
	Submission of Subcontractor Surveillance Audit Report (SSASS)	Unstructured	PM 30-20 69	(1 ED	.adf	Management Plan									
0.128	Submission of Corporate Surveillance Audit Report (CSADS)	Undructured	PM_10_20_69	FL80	pdf	Management Plan									_
.1.3	System Assurance Section Assurance Plan	Unstructured	PM 40 50 03												
0.13.1	Submission of Minutes of System Assurance Review Meeting No. 1	Undoctored	PM 40 50 03	F) 60	ad!	Management Plan		133623		7.6 or 21					11296-40
0.133			11010000	100	37										-
0.134															
1.4	No.														
	Submission of Risk Management Man, Risk Standard and Procedures	Unstructured	PM 60 60 75	FI 80	adi	Management Plan		29-(49-23		7-kur-23					11296-8
0.1.4.2	Submission of Risk Management Plan (Rev 01)	Shahractured	PM 60 60 75	F1 80	adf	Management Plan									_
0.143	Minute of Project Delivery Rait Morishop No. 3 Moretty Not Progress Report Aug 2023	Unstructured	PSI 60 60 75 PSI_60_60_75	F1 80	.ndf	Management Plan		29-lue-23		7-bur-21					11296-40
0.145	Monthly Misk Progress Report Sep 2023	Unstructured	PM 60 60 75	F1.80	atf	Management Plan Management Plan		23-jun-23		2.hus.21					11296-89
0.146		Unstructured		ri 80	adl	Management Plan		1730712		1 100000					
0.147	Nitrades of Project Delivery Fish Worlshee No. 2	Unstructured	PM 60 60 75	F1 80	adf	Management Plan		29-ium-23		7-hur-23					11286-4
0.148	Minutes of Project Delivery Risk Workshop No. 3	Unstructured	PM 60 60 75	FI BD	.adf	Management Plan									
0.148	Minutes of Project Delivery Fish Works No. 4	Unstructured	PM_60_60_75	FL.80	aff	Management Plan									-
.15	Human Factor	Unstructured	PM 60 60 75	n se	**										_
0.15.1	Reminetion of Contractor's Labour Officer Submission of Size Transportation Vehicles (with drivers)	Unductured	PM_60_60_75	0.60	adf	Management Plan Management Plan							_		+
1.6	Crainstructal	- Constitutes	PAGE DO S	POSE.	94	marugement Pun									_
0.1.6.1	Submission of Environmental Management Plan	Unstructured	PM_60_10_75	FL80_60	adf	Management Plan		10-Aug 23		3.0 m 23					11296-4
0.1.6.2	Submission of Contract Specific Environmental Monitoring and Audit (SMSA) Manual	Systectured	PSI 30:30 26	FL 80_60	ad!	Management Plan		15-14-25		7-har-23					11266-8
0.1.63	Submission of Nobe Management Plan	Shotnetured	PM 60 10 75	F1 80 90	adf	Management Plan		10-14-23		3-Aur-22					11296-8
0.184	Tree Risk Assessment of One Affected Tree Bombax cells inside The Works Area of Pedestrian Link Connecting Pair Tal Street and S	Unitractured	PM 60 10 75	F1 80 60	adf	Management Plan									-
0165	Monthly (MAA Report No. 10)	Unstructured	PM 60 10 75 PM_60_10_75	F1 80 60 F1,60,60	ad!	Management Plan									-
0.167	Construction/Relat Permit (CW 451128-22)	Undoutured	PM 60 10 75	FI 80.60	92	Management Plan	_						_	_	-
0.168	Northis EMBA Report No. 103	Websetured	PM 60 10 25	F1 80 90	adi	Management Plan Management Plan									_
					-										
0.1.6.10															
1.7	Roarces														
0.171	Salambalan of Contractor's Creambalton Chart	Unstructured	PM 60 20 55	FI 50 30	adf	Nomination of Sestem Assurance	Menager								_
0.17.2	Nondration of Staff	Unstructured Unstructured	PM 60 20 55 PM 60 20 55	FI 50 30 FI_50_30	ad!	Nomination of System Assurance Nomination of System Assurance						_	_	_	-
0.134	Numination of Salety Personnel (Salety Manager)	Websitzed	PM 60-20.55	FL 50_30	ast'	Noneiration of System Assurance									_
0.175	Semiration of Saleta Personnel (Saleta Officer)	Systematured	PM 60 20 33	FI 50 30	adi	Nonination of System Assurance									_
0.17.6	Nomination of Salata Personnel (Stocharter)	Unstructured	PM 60-20-55	FI 50 30	.adf	Nomination of Sestem Assurance									
	Nomination of Public Balations Officer	Unstructured	PM 60-20-55	FI 90 30	.edf	Nomination of Switzen Assurance									
0.178	Nomination of Cycelty Monager	Unstructured	PM_60_20_55	FL_50_30	.pdf	Nonitation of System Assurance									
0.17.0	Reminution of CPUU  Reminution of CPUU	Unstructured	PM 60 20 55 PM 60 20 55	FI 50 30	adi adi	Nomination of System Assurance Nomination of System Assurance							_	_	-
0.17.0	Proposed driver's coalification and ensertence	Unitractured	PM 60 20 33	F1 50 30	ad!	Nomination of System Assurance									+
0.17.12	Nomination of Planner	Unstructured	PM 60 20 55	FI 90 30	adf	Nomination of System Assurance	Monager								_
0.1.7.13	Numbration of Flamming and Programming Manager	Systructured	PM 60 20 55	FL 50_30	all	Nonlination of System Assurance	Minager								-
0.1.7.14	Numination of T4	Unstructured	PM 60 20 55	FI 50 30	adf	Nonisation of System Assurance	Minager								
0.17.15	Nomination of Human Factor Specialist	Systructured	PM 60:20:33	FI 50 30	adl	Nomination of System Assurance	Monagor								_
0.17.16		Unstructured	PM 60 20 55	F1 90 30	adf	Nomination of Sestem Assurance Nomination of Sestem Assurance									-
0.17.17	Ricerination of System Assurance Manager Ricerination of CPUID From Kong Sang and Rig Tong Chia Henryl	Unstructured Unstructured	PM 60 20 55 PM 60 20 55	FI 90 30 FI_90_30		Nomination of System Assurance Nomination of System Assurance	Monaner		_				_	_	+-
0.13.19	Reminister of Survey Assistants (Lee Tee King)	Undirectured	PM 60 20.55	FI 50 30	28°	Nonembor of System Assurance	Monager								_
0.17.20	Nomination of DCSHS Soon Leader and town recorders	Systematured	PM 60-20-55		ati	Nonination of System Assurance	Minager								_
0.1.7.21	Nomination of Independent Consultant for Condition Survey	Unstructured	PM 60-20-55	FI 50 30	adf	Nomination of System Assurance	Minaper								
0.1.7.22		Unstructured		F1 50 30	.edf	Nortination of System Assurance	Monager								
0.1.7.23	Nomination of Sovironmental Team (ST) and ST Leader (Mandy To)	Undructured	PM_60_20_SS		.pdf	Nomination of System Assurance									
0.1.7.24	Noninatics of Assistant Construction Manager	Systructured	PM 60:20:55		all	Nonination of System Assurance						_	_	_	_
0.1725		Unstructured	PM 60 20 55 PM 60 20 55	FI 50 30 FI 50 30	adi .	Nomination of System Assurance Nomination of System Assurance									+
	Reminution of Survey in-change	VT III VILLEY	Per 80 10 11	11 NO 20		MATERIAL STREET ASSESSED.	Annual Control								

_	DELIVERABLE PRODUCTION SCHEDULE			Constructor's Sub	mission Schedu	ile									
		Contract No:		PYCs Representative: "		I									
				Inform (unstructured and	ation details distructured information)										
(ID of project stage, group of deliverables, deliverable or information continue (IC), i.e. file)	NAME (of project stage, group of delivarables, delivarable or information container (C) / flex)	STRUCTURE OF INFORMATION (btructured - can be interpreted by a muchine unstructured - must be interpreted by a human)	CLASSIFICATION CODE (Uniclines 2015)	FORM (form of presenting information based on Uniclass 2015)	FORMAT (file format)	DESCRIPTION (plain language)	CONTENT COMMENTS (specific requirements for the contents)	Target Submission Date PYC to MTR	Target Submission Date To STA	Target Approval Date	REFERENCE (Jamphale or other reference to be used to prepare information)	TARGET SUBMISSION MLESTONE (weeks after appointment starting date)	APPROVAL MILESTONE (weeks after submission milestone)	SUBMITTING PARTY CODE (Contractor / Subcontractor)	Programme ID
00.11	Sahira & Health		PM 60 70 95												
	Submission of Site Pensonnel Uniform Design Submission of Uniform Changing Facilities	Unstructured	PM 60 70 95	FI.80	.52°	Management Plan Management Plan							_	-	
0.113	Submission of Safety and Health Management Plan	Overactured	PM 60 70 12	FI 80	adf	Management Plan									
0.1.14	Submission of Energency Action Plan	Systractured	PS4 80 50 30	ri 80	e#	Managersort Plan									
0.1.1.5	Submission of Air Quality Management Plan (AQMP)	Unshackered	PSI 60 70 55	ri 80	adi	Management Plan									
0.136	Submission of Health & Safete Plan Welfare and Higgiese Plan	Unstructured Unstructured	PM 80 70 37 PM 60 70 37	FI 80	adf	Management Plan		1014/23		Adap-23			_		11386-WVF-01820
	Submission of Creegonsy Plan for Park Colleges	Overstund	PSI 80 50 30		98'	Management Plan							_		
			PM 80 50 30		atl	Management Plan									
0.1.1.10	Submission of Otto Management Plan		PM 60 70 27	F1 80	adf	Management Plan									
0.13.11	Report for Drill in relation to five occur at Temperary Site Office	Unstructured	PM 60 70 17	F1 80	aff	Management Plan									
0.121	Quelty Submission of Quelta Flan	Unstructured	PM 30 20 89	n so	adi	Management Plan									
0.12.2	Submission of Contractor's Submission Schedule	Unstructured		FI 80	adf	Management Plan									
0.12.3	Submission of Survey Quality Flan	Unstructured	PM 10 20 68	FL80	981	Managersont Plan									
	Submission of proposed action plans for CQA 11286 ES	Undructured	PM 10-20-69 PM 10-20-69	FL80	ad!	Management Plan									
0.125 0.126	Active consistion record for Contractor Coality Audit (CQA 11286-91) Submission of Internal Audit Report PSACU	Unstructured Unstructured	PM 30 20 89	ri 80	od!	Management Plan Management Plan									
0.13.7	Submission of Subscript rather Surveillance Audit Recort (SSASS)	Unstructured	PM 30 20 68	(1 8D	adf	Management Plan									
0.12.8	Submission of Corporate Surveillance Audit Report (CSAD1)	Unerschied	PM_10_20_69	FL80	adf	Management Plan									
60.13	System Assurance														
0.13.1	Sestem Assurance Flori Submission of Minutes of System Assurance Review Meeting No. 1	Unstructured	PM 40 50 03 PM 40 50 03	FI SD	ad'	Management Plan		153625		7.6se.21				_	11296-MVP-01950
0.133	SARTHAN D'ANNAG D'AYART ANAGAS PEREN MENTE NA 1	Vicinities	PACE 30.33	PLSE.	34	management Past									
0.13.4															
50.1.4	No.														
	Submission of Rok Management Man, Rok Standard and Procedures Submission of Rok Management Plan (Roy 01)	Unstructured	PM 60 60 75 PM 60 60 75	FI 80	atl	Management Plan		29-ion-23		7-har-23					11296-WVP-01550
	Submission of Risk Management Plan (Rev CS) Minute of Project Delivery Risk Workshop No. 1	Unstructured	PM 60 60 75	FI BD	adf	Management Plan		29-0xe-23		7-bur-21	_		_		11286-MVP-01570
	Monthly list Progress Report Aug 2022	Systructured	PM_60_60_75	FL 80	all	Management Plan									
0.1.4.5	Monthly Risk Progress Report Sep 2023.	Unstructured	PM 60 60 75	FL80	adf	Management Plan		23-(sm-23		7-hus-21					11296-mvP-01390
0.146	Morthly Risk Progress Report Dct 2023		PSI 60 60 75		pėl	Management Plan									
0.147	Minutes of Project Delivery Etal Workshop No. 2 Minutes of Project Delivery Etal Workshop No. 3	Unitroduced Unitroduced	PM 60 60 75 PM 60 60 75	0.80	adf	Management Plan		29-jun-23		7-hur-22					11286-WW-01570
0.148	Minutes of Project Delivery Risk Works No. 4	Undustried	PM_60_60_75	0.50	20	Management Plan									
60.15	Hamon Factor														
	Nomination of Contractor's Labour Officer	Unitractured	PM 60 60 75	0.60		Management Plan									
0.152	Submission of Site Transportation Whicker (with drivers)  Continuoruntal	Undructured	PM_60_60_75	H_MD	.921	Management Plan								-	
0.16.1	Submission of Environmental Management Plan	Unstructured	PM_60_10_75	FL80_60	adf	Management Plan		10-Aug 21		3.0 m 23					11296-MVP-01290
0.1.6.2	Submission of Contract Specific Environmental Munitaring and Audit (EMBA) Manual	Systractured	PSI, 30: 30: 29	FL 80, 90	all	Management Plan		13-14-25		7-hus-23					11266-WVP-01660
		Systestured	PM 60 10.75	F1 80 60	ad	Management Plan		10-14-23		3-hur-23					11296-WVP-01270
0.18.4	Tree Risk Assessment of One Affected Tree Bombax calbulistide The Works Area of Pedestrian Link Connecting Fak Tal Street and S Streets (SASA Search Str. 101	Unstructured	PM 60 10 75	F1 80 00	adi adi	Management Plan								_	
	North (Mis Rept No. 10)	(instructured	PM 60 10 75	F1 80 60	net .	Management Plan								_	
	Construction-Noise Pennit (GW-451128-20)	Systematical	PSE 60:10.75	FL 80.60	atf	Management Plan									
0.168	Month's (MSA Report No. 10)	Webstured	PM 60 10 75	FI 80 60	pdl	Management Plan									
0.140															
60.17	Acources														
0.17.1	Submission of Contractor's Organisation Chart	Unstructured	PM 60 20 55	FI 50 30	.ndf	Nomination of Sestem Assurance	Vinasir								
	Nomination of Staff	Unstructured			-adf	Noreitation of System Assurance	Vonaner								
0.17.3		Unstructured	PM_60_20_55	FL90_30	pdf	Nomination of System Assurance	Vonager							_	
0.174	Nomination of Saleta Personnel (Saleta Manager) Nomination of Saleta Personnel (Saleta Officer)	Unstructured Unstructured	PM 60 20 55 PM 60 20 55		ad	Nomination of System Assurance Nomination of System Assurance								-	_
0.17.6	Nomination of Sakto Personnel (Site Nurse)	Unstructured	PM 60 20 55	FI 50 30	adf	Nomination of Sestem Assurance									
0.1.7.7	Nomination of Public Relations Officer	Unstructured	PM 60 20 55		.edf	Normination of Sestem Assurance	Vonaner								
0.178	Nonination of Cyality Monager	Unstructured	PM 60-20-55 PM 60-20-55	FL 56_30 FL 56_30	.925	Nomination of System Assurance	Vorager							-	
	Nomination of Temporary Worls Coordinates  Nomination of CPUI		PM 60 20 55 PM 60 20 55	FI 50 30	ad ad	Nonination of System Assurance Nonination of System Assurance	Visiger						_		
0.1.7.11	Proposed driver's sualification and searchings	Shabactured	PM 60 20 55	F1 50 30	ad!	Norwination of System Assurance	Vonacer								
		Unstructured	PM 60 20 55	FI 50 30 FI 50 30	.adf	Nomination of System Assurance	Vonaner								
0.1711		Undouted	PM 60 20 55 PM 60 20 55		-46	Nomination of System Assurance Nomination of System Assurance									_
			PM 60 20 55 PM 60 20 55		adi adi	Nomination of System Assurance Nomination of System Assurance					_				_
	Reminution of Role Manager	Unshartured	PM 60 20 55		ad!	Nomination of Sestem Assurance									
0.17.17	Romination of System Assurance Manager	Unstructured	PM 60 20 55	FI 50 30 FI 50 30	.adf	Nomination of System Assurance I	Vonamer								
0.1.7.18	Hernicetice of CPUN/Poor King Sang and Ng Tong Chiu Henry)	Undructured	PM 60 20 55	FI 50 30	25	Nomination of System Assurance	Vonager								
	Numination of Survey Assistants (Lee Tile King) Numination of DCSMS Tourn Leader and tourn reumbers		PM 60 20 55 PM 60 20 55	FI.50.30	ad ad	Nomination of System Assurance Nomination of System Assurance							_	-	_
0.1.7.21	Numeration of DCSMS Tourn Lauder and tourn reundors. Numeration of Independent Consultant for Condition Survey.	Unstructured	PM 60 20 55	FI 50 30	.001	Nomination of System Assurance	Vinapr								
	Nomination of ICE/ISS & BGE1	Unstructured	PM 60 20 55		.edf	Noreinstion of System Assurance	Vonaner								
0.1.7.23	Nomination of Environmental Team (ET) and ET Leader (Mandy To)	Unstructured	PM_60_20_55	FL 90_30	adf	Nonitation of System Assurance	Vonager								
	Noninctice of Assistant Construction Manager		PSI 60:20:55		adf	Nonination of System Assurance	Visiager								_
	Reministre of Survey Manager	Unstructured	PM 60 20 55	FI 50 30	adi	Nomination of System Assurance I									
0.1.7.26	Nomination of Survey In-change		PM 60 20 55			Nomination of System Assurance									

BIM Execution Plan Page 54 of 60

# Appendix B – Task Information Delivery Plan (TIDP)

	DELIVERABLE PRODUCTION SCHEDULE			Constructor's Sub	mission Schedu	ile									
		Contract No:		PYCs Representative:	ation details										
10	NAME (of project stage, group of deliverables, deliverable or information container (C) / file)	STRUCTURE OF INFORMATION	CLASSIFICATION CODE (Uniclass 2015)	(unstructured and	FORMAT (file format)	DESCRIPTION (plain language)	CONTENT COMMENTS	Target Submission Date	Target Submission	Target Approval Date	REFERENCE	TARGET	APPROVAL	SUBMITTING	Program
ID f project stage, group fiverables, deliverable information container (C), i.e. file)	(of project stage, group of deliverables, deliverable or information container (C) / file)	STRUCTURE OF INFORMATION (structured - can be interpreted by a machine unstructured - must be interpreted by a human)	(Uniclase 2015)	FORM (form of presenting information based on Uniclass 2015)	(file formal)	(plain language)	CONTENT COMMENTS (specific requirements for the contents)	PYC to MTR	To STA		(Jamplate or other reference to be used to prepare information)	SUBMISSION MLESTONE (weeks after appointment starting date)	APPROVAL MILESTONE (weeks after submission milestone)	SUBMITTING PARTY CODE (Contractor / Subcontractor)	
11.11	Selvin & Roadh														
1112 1113	Under State Der	Overstund Overstund	PM 60 70 95 PM 60 70 95 PM 60 70 95 PM 80 50 90 PM 80 70 95 PM 80 70 95	FI 80 FI 80	20° 20°	Management Plan Management Plan									
0114 0115 0116	Submission of Energians Action Flan Submission of Air Guello Manuscreent Plan (AQMP) Submission of Franklin & Subtra Res	Understand Understand Understand	PM 80 50 30 PM 60 70 95 PM 60 70 12	n 80 n 80	201 201 201 201 201 201 201 201	Management Plan Management Plan Management Plan		10.14-23		hard.				_	11206-494
0.13.7	Welfare and Highest Plan Submission of Energywy Plan for Plant Colleges	Unstructured	PM 60 70 17 PM 80 50 30	FLSD FLSD	pdf pdf	Management Plan Management Plan									
0.1.1.9 0.1.1.10	Submission of Emergency Flee for Ground Settlement and Collapse Submission of Criss Management Plan	Undoubured Undoubured	PM 60 70 12 PM 60 70 12 PM 80 50 80 PM 80 70 12 PM 60 70 12	n 80 n 80	ad ad	Management Plan Management Plan									
0.12.1	Swifty Setrous of Guilto Ren	Vertextured	PM 20 20 69			Management Plan									
0.12.1 0.12.2 0.12.3 0.12.4	Submission of Contractor's Submission Schedule Submission of Sunney Quality Rism  Submission of Sunney Quality Rism  Submission of Sunney Quality Rism  Submission of Sunney Sunney Sunney Rism  Sunney Sunney Sunney Sunney Rism  Sunney S	Vestractured Vestractured Vestractured	PM 30 20 89 PM 40 60 00 PM 30 20 89 PM 30 20 89 PM 30 20 89 PM 30 20 99 PM 30 20 99 PM 30 20 99 PM 30 20 98	FI BD FI BD	.98	Management Plan								_	
0.125 0.125	Setting consultation record fire Contraction Could's Audit (COA 11286-01)  Submission of Frinternal Audit Record IPS-ACI)	Unstructured Unstructured	PM 10 20 89 PM 10 20 89	n 80	at at	Management Plan Management Plan								_	
0.13.7	Submission of Substantination Surveillance Audit Report (SSADS) Submission of Corporate Surveillance Audit Report (CSADS)	Unstructured Unstructured	PM 10 20 69 PM_10_20_69	FL 80	.at .at	Management Plan Management Plan									
	Submission of Minutes of System Assurance Review Meeting No. 1	Unstructured	PM 40 50 03 PM 40 50 03	F1 80 F1 80	od! pdf	Management Plan Management Plan		1516.75		7.6 or 71					11296-4
0.133 0.134	Lead of the Section o														
0141 0142	Submission of Pasi Management Kan, Bob Standard and Procedures  Submission of Pasi Management Flor (Par-01)	Undrustured Undrustured	PM 60 50 75 PM 60 60 75	H 80	281 281	Management Ples		29-jun-23		7-har-22					11286-8
0154 4 0141 0143 0143 0146 0145	Minute of Project Delivery Risk Workshap No. 3 Nounthly Nest Progress Report Rug 2023	Unitructured Unitructured	PM 60 60 75 PM 60 60 75	F1 80 F1,80	.pli .pli .pli .pli .pli .pli .pli .pli	Management Plan Management Plan		19-tun-21		7-au-21					11296-#
0145 0146 0147 0148 0148	Monthly Risk Progress Report Sep 2018 Monthly Risk Progress Report Sep 2018 Monthly Risk Progress Report Set 2018 Monthly Risk Progress Report Set 2018 Monthly Risk Risk Risk Report Set 2018 Monthly Risk Risk Risk Risk Risk Risk Risk Risk	Undrustured Undrustured	PM 60 60 75	FI 80 FI 80	28 28 24 24 24 24 24 24 24 24 24 24 24 24 24	Management Plan Management Plan		29-jun-23 29-jun-23		7-har-23 7-har-23				_	11286-8
0.148	Minutes of Project Delivery Risk Workshop No. 3 Minutes of Project Delivery Risk Works No. 4	Statractured Onstructured Statractured	PM 60 60 75 PM 60 60 75	F1 80 F1 80 F1 80	.adf .pdf	Management Plan Management Plan									
0151	Human Facior  Reminster of Contractor's Labour Officer  Contractor of Contractor's Labour Cofficer  Contraction of Contractor's Making to Contractor  Contraction of Contractor Contractor  Contraction of Contractor  Contrac	Onstructured Onstructured	PM 60 60 75 PM 60 60 75	F1 80	ad! ad!	Management Plan Management Plan									
0.148 5 0.151 0.152 4 0.161 0.162	Continuorental Subministra of Contramental Management Plan.	Unstructured	Pol. 60 10 75 Pol. 80 10 26			Management Plan Management Plan		20 Aug 23		3 Aug 23					11296-40
0.163	Submission of Contract Specific Environmental Manifesting and Audit (EMBA) Manual Submission of Notice Management, Plan.	Systematured Systematured	PM 60 10 75	F1, 80, 60	921 931 931	Management Plan Management Plan		20-Aut-23 13-14-23 10-14-23		3-har-23 7-har-23 3-har-23					11296-00 11296-00 11296-00
0165	North (NAA Rept No. 10) North (NAA Rept No. 10)	Unstructured Unstructured	PM 60 10 75 PM 60 10 75	F1 80 60	.pdf	Management Plan Management Plan								_	_
0.167	Construction No. In Construction (Inc. 1997) (Inc. 199	Shiftschured Shiftschured	PM 60 10 75 PM 80 10 75 PM 60 10 75 PM 60 10 75 PM 60 10 75 PM 60 10 75	F1 80 90 F1 80 90 F1 80 90	981 981 981	Management Plan Management Plan									
	Property														
0.17.1 0.17.2 0.17.2 0.17.4	Beantye. Salt-halor of Contractor's Countsellen Cart Interducina of Salt Salt Interducina of Salt Interducina of Salt	Unstructured Unstructured	M 6 20 25 M 7 20 25	FI 90 30 FI 90 30 FI 90 30	.501 .501 .501 .501	Nomination of System Assurance I Nomination of System Assurance I	Sinasor Sinasor								
0.173 0.174		Undrustured Undrustured Undrustured	PM 60 20 55 PM 60 20 55 PM 60 20 55	FI. 50. 30	92' 93'	Nomination of System Assurance I Nomination of System Assurance I Nomination of System Assurance I	tonager Sonager Sonager							_	=
0.175 0.176 0.177	Nomination of Salute Personnel (Site Name) Nomination of Public Deletions Officer	Unstructured Unstructured	PM 60 20 55 PM 60 20 55	FI 90 30 FI 90 30	.edf	Nomination of System Assurance I Nomination of System Assurance I	Sinazor Sinazor								
0.178 0.179 0.1710	Nonination of Cyulley Monager  Permination of Foreign Avenue Coordinates  Remination of CPUII	Undoctored Undoctored	PM 60-20-55 PM 60-20-55 PM 60-20-55	FL 50-30 FL 50-30	921 931	Nomination of System Assurance I Nomination of System Assurance I Systemation of System Assurance I	Surager Surager Surager								=
0.17.11	Account of the Account below Managed  Account of the Account below  Account to the Account below  Account to the Account below  Account to the Account to the Account   Account to the Account to the Account   Account to the Account   Account to the Account   Ac	Unstructured Unstructured	PM 60 20 55 PM 60 20 55	FI 50 30 FI 90 30	201 201 201 201 201 201 201 201 201 201	Secretarion of Spitter Assessment Secretarion Se	Sinasir Sinasir								
0.17.14	Numbration of Flaming and Programming Manager  Teachastics of Fid.  Numbration of Homes Factor Secretaria	Understand Understand	PM 60-20-55 PM 60-20-55			Nomination of System Assurance II Nomination of System Assurance II Nomination of System Assurance II	turager turager turager								
0.17.16	Reministre of Bish Meneuer Reministre of System Assurance Manager	Unstructured Unstructured	PM 60 20 55 PM 60 20 55	FI 50 30 FI 50 30	.edf	Nomination of Sestem Assurance I Nomination of Sestem Assurance II	Senator Senator								
0.17.18 0.17.19	Remindrice of CPUIDPoon King Song and Rg Tong Chia Henryl Remindrice of Survey Assistants (see The King) Remindrice of Survey Assistants (see The King) Remindrice of Survey Assistants (see The King)	Undoutured Undoutured	PM 60 20 55 PM 60 20 55	FI_50_30 FI_50_30	보면 보면 보면 보다	Nomination of System Assurance I Nomination of System Assurance I	tonager Smager								
01714 01715 01716 01717 01718 01719 01719 01720 01721 01721	Nomination of Indexembert Consultant for Condition Survey Nomination of ICE/ISSE & ISSE	Unstructured Unstructured	PM 60 20 55 PM 60 20 55	FI 50 30 FI 50 30	adf adf	Nomination of System Assurance I Nomination of System Assurance II	Smaor Smaor								
0.17.29 0.17.24 0.17.25 0.17.26	Nonington of Englanmental Times (E) and ET Leader (Mandy To) Reprinciple of Associate Construct tim Manager Reprinting of England Reprint	Undructured Undructured	PM 60 20 55 PM 60 20 55 PM 60 20 55 PM 60 20 55	FI_90_30 FI_90_30	.92f .98f	Nomination of System Assurance I Nomination of System Assurance I	Sinaper Sinaper							_	_
0.1326	Nominative of Survey In-chasse	Unstructured	PM 60-20-55	FI 50 30	.adf	Nomination of System Assurance I	linaor .								-
0.112.1 1.23 0.112.1 0.112.2 0.112.3 0.112.8 0.112.4 0.112.5	Control Contro	Unstructured	PM_30_20_34 : Digital Construction	Sto FL 60_85 : Survey (SU)	FOS	Report -	Survey of existing utilities	7-1623							11286-
0.1333	Method Statement for Institutestation installation and Monitoring  Nethod Statement for Condition Survey	Unitractured Unitractured	100 to 20 22  10	FI 80 50 FI 80 50 FI 80 50	30f 30f 30f	Communicate Method Communicate M								=	=
0.133.4 0.133.5	Method Statement for Trial Pit and Treech-Expansion Method Statement for General Site Cleanance	Unitractured Unitractured	MM 60 20 22 MM 60 20 22	FI 80 50 FI 80 50	.ed	Construction Mathod Construction Mathod									
0.133.7	Submission of Sub-contract Management Flan Nethod Statement for Houseling Relocation works	Untrictured Unstructured	PM 60: 20, 22 PM 60: 20: 22	FI 80 50 FI 80 50	all all	Construction Method Construction Method									11286-1
0.1317 0.1318 0.1319 0.13310 0.13311 0.13111 0.13111	Method Statement for Fixed Procention and Mittadion Method Statement for Grand Preshilling Works	Unitractured Unitractured	PM 60 20 22 PM 60 20 22	FI 80 50 FI 80 50	.edf	Construction Method Construction Method		15 at 23		9 Aur 22					11286-1
0.119.12	topicated ITF for Method Statement for Personal of Underground Obstruction  (bill Rg Information By JAMI)	Unstructured Unstructured Unstructured Unstructured Unstructured	PM 60 20 22 PM 60 20 22	FL 80_50 FL 80_50	987 981 991 -201 991 991	Construction Method Construction Method		21-Aun-23 32-Aun-23 35-Aun-23 27-aun-23 10-aun-23		25/80-23 13/01-23 23/4-23 13/01-23				=	11286- 11286- 11286- 11286- 11286-
0.133.14 0.133.15 0.133.16 0.133.16 0.133.17 0.133.18 0.133.19 0.133.20 0.133.20 0.133.21	Method Statement for Installation of Standalps and Piccometer Submission of Method Statement for Decision of PM's Office and Contractor's Office	Unitractured Unitractured	MM 60 20 22 MM 60 20 22	FI 80 50 FI 80 50		Construction Method Construction Method		27-iun-22 10-se-23		7-14-22 13-011-23				_	11286
0.1.18.17 0.1.18.18	Nethod scaleshor for the espans work.  Task Specific Work Procedure for Fricial PL & Trench exclusion and removal of underground electractice.  Supplementate Pro-process Leanst and Dwath of Approach Lights for Wethod Statement for Pre-processing Works.	Unitractured Unitractured	PM 60 20 22 PM 60 20 22	FI 80 50 FI 80 50	25 26 26 26 26 27 26 26 26 26 26 27 28	Construction Method Construction Method								=	=
0.139.19 0.139.20	Procedures for Crans Assemble for Bored Piling Works Method Statement of Bored Pilin Works	Unitractured Unitractured	MM 60 20 22 MM 60 20 22	FI 80 50 FI 80 50	.elf	Construction Mathod Construction Mathod									
0.139.22	Task See/Fit Work Procedure for CCTV Inspection for Existing Orania Nethod Statement for Constitution of Coverol Mickey at Pair Tai Street Northod Statement for Illinocom folia Sounder find	Untractured Untractured	PM 60-20-22 PM 60-20-22	FI 80 50 FI 80 50	ati	Construction Method Construction Method		151625		1.6xx.21				_	11786
0.139.24	Niethod Statement for Soric Logging Test Niethod Statement for Pipe Pile Works	Unitractured Unitractured	MM 60 20 22 MM 60 20 22	F1 85 30 F1 85 30 F1 80 30 F1 80 30	.98 .98 .98 .98	Construction Method Construction Method									11286
0.1.13.26	Task SeecFit Work Procedure for Communical of Drebar for Car Park for PMYs Office and Contractor's Office Nethod Statement for Temporary Association Institutes.	Unstructured								84431					
0.134.2 0.134.1 0.134.2 0.134.3	Material Submission of Bereceite Centeré Grout titlu Material Suggie	Unstructured Unstructured	PM_60_10_65 PM_60_10_65	FL90_87				4-ai-21 11-bio-21 15-Aur-23		2-12-21 21-5m-21 13-0x1-23					11284 11284 1128
31343 31344	Material Testing Materials Test Report			FL 90_97	.pdf			11.6m/21 15.6m/23 9.5m/23		2-14-33 70-3-0-23 13-501-23					
31346		Undructured	MM 60 10 65 MM 60 10 65	FI_50_82 FI_50_82 FI_50_82 FI_50_82	.921 .931 .931			D-SW-D		2-42-31 Ph.Sec.23 13-0xt-23					1128
	Salar-island of overlatocement supplier - NV Salar-island of overlatocement supplier - VSC Salar-island of overlatocement supplier - WMS	Units state of Units where Units state of Units sta	PM 80 10 85 PM 80 10 85 PM 60 10 65 PM 60 10 65 PM 60 10 65	FI 50 87 FI 50 87 FI 50 87 FI 50 87 FI 50 87 FI 50 87 FI 50 87	.001 .981 .991 .991 .001			D-SW-D		244/31 75.5m/21 33.9xt-23					1128
0.1348	Submission of metal processor augustes - See  Submission of metal processor augustes - VSC  Submission of metal processor augustes - VSE  Submission of metal processor augustes - VSE  Submission of metal processor augustes - VSE  Through Euthoriston CTS for Print Load Text  Through Euthoris	Onstructive Unitroduced Unitroduced Unitroduced Unitroduced Unitroduced Unitroduced Unitroduced Unitroduced Unitroduced	MM 80 10 85 PM 80 10 85	自使記 日発記 日発記 日発記 日発記 日発記 日発記 日発記 日発記	901 907 907 907 907 907 907 907			D-SW-D		644-31 75.5m-21 13-50-22					1128 1128 1128 1128 1128
3.134.8 3.134.9 3.134.10 3.134.11 3.134.12	controller or interference supple. Visit.  Alternative or interference supple. Visit.  Alternative discription or discripti	Versionare	MM 60 10 65 PM 60 10 65	\$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52 \$1.50,52	98 98 98 98 98 88 88 98			D-SW-D		244-73 75-80-71 13-50-71					1128
11348 11349 113410 113411 113412 113413 113414	Laborator investment trades on  Activation of the Control of the C	Contraspined	PM 80 10 95 PM 80 10 95 PM 80 10 95 PM 80 10 05	10, 00, 07 10, 00, 07	98 98 98 98 98 88 88 98			D-SW-D		244-23 75-5m-21 13-5st-23					1128 1128 1128 1128 1128
1348 1349 13410 13410 13411 13412 13414 13414 13415 13416	Antonio mentionera salari 200  Internati antonio mentionera salari 200  Internationera salari 200  Internati	Consistence Consis	MM 88 10 65 MM 89 10 65 MM 69 10 10 55 MM 69 10 10 55 MM 69 10 10 55 MM 69 10 65	10.06.87 10.50.87	98 98 98 98 98 88 88 98			D-SW-D		64421 Pister 21 13-50-21					1128 1128 1128 1128 1128
1348 1349 13410 13410 13411 13412 13413 13414 13415 13416 13417 13417 13418 13419	Contract of Contra	Contraction of Contra	MM 80 10 05 MM 10 15	10, 06, 27 10, 50, 27	98 98 98 98 98 88 88 98			9-2ee-23		64431 756671 335673					1128 1128 1128 1128 1128 1128 1128
1 348 2 329 2 349 1 3410 1 3411 1 3412 1 3412 1 3412 1 3415 1 3416 1 3416 1 3416 1 3416 1 3416 1 3416 1 3416 1 3416	And the second s	Ownerward	TML 82 (0.55)  MML 82 (0.55)  MML 82 (0.55)  MML 82 (0.55)  MML 83 (0.55)  MML 83 (0.55)  MML 83 (0.55)  MML 83 (0.55)  MML 84 (0.55)  MML 85 (0.55)		수보 전 2년 2년 2년 2년 2년 2년 2년 2년 2년 2년			9-2ee-23		64421 756071 1350121					1124 1124 1124 1124 1124 1124 1124 1124
1346 1340 13410 13411 13411 13411 13415 13415 13415 13416 13417 13416 13417 13418 13417 13418 13417 13418 13417 13418 13421 13421 13421 13421	Content of Anthony and Content of	Contracted	TML 82 (0.05)  MILL 83 (0.05)  MILL 83 (0.05)  MILL 84 (0.05)  MILL 84 (0.05)  MILL 85 (0.05)	10 (6) (2) (2) (3) (4) (4) (4) (4) (4) (4) (4) (4) (4) (4	100 100 100 100 100 100 100 100			9-2ee-23		64421 Phonys 1150c31					1121 1121 1121 1121 1121 1121 1121 112
1 MHB	And the second s	Commont of Commont of Common of Comm	THE SET US ST SE		100 100 100 100 100 100 100 100			9-2ee-23		64423 Khani 1904.0					1121 1121 1121 1121 1121 1121 1121 112
3.448 3.459 3.410 3.411 3.411 3.411 3.414 3.414 3.415 3.	And the second s	Controlled	MALES LOSS  MALES		100 100 100 100 100 100 100 100			9-2ee-23		64423 Non-17 1004-51					1121 1121 1121 1121 1121 1121 1121 112
1,144 8 1,245 9 1,241 10 1,241 11 1,241 11	And the second s	Special and Specia	March   10   10   10   10   10   10   10   1	1.66.2  1.66.2	98 98 98 98 98 88 88 98			9-2ee-23		64423 PSunt 110023					112 112 112 112 113 114 115 115 116 117 117
1,348 1,349 1,3410 1,3410 1,3410 1,3411 1,34	And the second s	Secretary Control of C	March 20   10   10   10   10   10   10   10	1.06.27 1.06.2	発展 2月 2月 2月 2月 2月 2月 2月 2月 2月 2月			9-5ee-23 9-5ee-23		4442 Noort 1002					112 113 114 115 115 115 115 115 115 115 115 115
1,048 1,049 1,0410 1,0410 1,0410 1,0411 1,04	And the second s	Comments  Commen	March 20   10   10   10   10   10   10   10	1.0.6.2   1.0.	発展 2月 2月 2月 2月 2月 2月 2月 2月 2月 2月			9-5ee-23 9-5ee-23		4423 PROST					112 113 114 115 115 115 115 115 115 115 115 115
1,948 1,949 1,9410 1,9410 1,9411 1,94	And the control of th	Section 19 Control 19	March 20   10   10   10   10   10   10   10	1.0.6.2   1.0.6.	発展 2月 2月 2月 2月 2月 2月 2月 2月 2月 2月			9-5ee-23 9-5ee-23		4425 1456-13 1456-13					1124 1124 1124 1124 1124 1124 1124 1124
1348 1349 13410 13410 13411 13	And the second s	Comments  Commen	March 20   10   10   10   10   10   10   10	1.0 d. 2.7 d. 2.	1987 1987 1987 1988 1988 1988 1988 1988			9-5ee-23 9-5ee-23		4425 A					
1346 1346 13410 13410 13410 13410 13411 13	And the second s	Section 19 Control 19	No. 20 Sept.	3 - 0.0 is in the control of the con				9-5ee-23 9-5ee-23		4213 110431					
1388 1389 13810 13810 13811 1381 13811 13811 13811 13811 13811 13811 13811 13811 13811 13811 138	And the second control of the second control	Secretary Control of the Control of	A	3. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0.				9-5ee-23 9-5ee-23		AUS III III III II II II II II II II II II					
1344 1344 1344 1344 1344 1344 1344 1344	And the second s	Comments  Commen			発展 2月 2月 2月 2月 2月 2月 2月 2月 2月 2月			\$ 500 23 \$ 500 23		AUS HOLES					
1345 1345 1345 1346 1346 1346 1346 1346 1346 1346 1346	And the second s			3. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0.				\$ 500 23 \$ 500 23		4213. 1100.12					
1 144. 1 145. 1 144. 1 144. 1 145. 1 144. 1 145. 1 144. 1 145. 1 144. 1 145. 1 144. 1 145. 1 144. 1 145. 1	A Company of the Comp	Section of the control of the contro		3 - 3 - 5 - 5 - 5 - 5 - 5 - 5 - 5 - 5 -				\$ 500 23 \$ 500 23		4227. 1104.12					
1144 1144 1144 1144 1144 1144 1144 114	And the second s	Section of the control of the contro		3 - 3 - 3 - 3 - 3 - 3 - 3 - 3 - 3 - 3 -				\$ 500 23 \$ 500 23		4223. 1100.12					
11 11 11 11 11 11 11 11 11 11 11 11 11	A Company of the Comp			3 - 0 - 0 - 0 - 0 - 0 - 0 - 0 - 0 - 0 -		More in the man of the		\$ 500 23 \$ 500 23		4227. 3100.12					
1.1 May 1.1 Ma	And the second s	Section of the control of the contro		3 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		More in the man of the		\$ 500 23 \$ 500 23		ALEST LAND AND AND AND AND AND AND AND AND AND					1134 1134 1134 1134 1134 1134 1134 1134
1.1146 1.1146	A control of the cont			3 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		More in the man of the		\$ 500 23 \$ 500 23		######################################					
11 11 11 11 11 11 11 11 11 11 11 11 11	A Company of the Comp	Secretary of the control of the cont		3 - 3 - 5 - 5 - 5 - 5 - 5 - 5 - 5 - 5 -				\$ 500 23 \$ 500 23		ALEST LINE AND					1128 1128 1128 1128 1128
11114 1114 1114 1114 1114 1114 1114 11	And the second s	Section of the control of the contro		3 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		More in the man of the		\$ \$50.23		ALEST					
11.11.11.11.11.11.11.11.11.11.11.11.11.	Section of the control of the contro	Total Control of Contr		3 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		More in the man of the	The state of the s	\$ 500 23 \$ 500 23		ALERA LA					

BIM Execution Plan Page 55 of 60

# Appendix C – LOD Matrix

# 3.5.2 High Responsibility Matrix are:

Table 3-5 High Responsibility matrix of 26 BIM uses (except no.6, 7 and 12, 25).

	Legend of Res	sponsibility matrix	
Responsible	Action	Contribute	Informed
R	Α	С	I
Person who is responsible completing the task	Person who is taking actions on the task(s)	Person who will be communicated with regarding the decision- making process and specific tasks	Person who will be updated on decisions and actions during the project

	Le	vel 1	Resp	onsibi	ility m	atrix					
No	BIM Use	Client	мсрм	мсвм	мсвс	Eng.	qs	so	SY	EO	QM
1	Design Authoring	1	- 1	R	Α	С					
2	Design Review	С	1	R	Α	- 1					
3	Project Deliverables (incl. Drawings)	- 1	- 1	R	Α	С					
4	Existing Conditions Model	I	- 1	R	Α	I			С		
5	Sustainability Evaluation	I	- 1	R	Α					С	
6	Site Analysis										
7	Space Programming			R	Α						
8	Cost Estimation (5D Model)	-1	- 1	R	Α		С				
9	Spatial Coordination (3D)	1	- 1	R	Α	С					
10	Engineering Analysis	С	- 1	R	Α						
11	Facility Energy Analysis	С	- 1	R	Α						
12	Building Code Validation										
13	Phase Planning (4D Model)	- 1	С	R	Α	С		С			
14	Digital Fabrication	I	- 1	R	Α	С					
15	Site Utilisation Planning	1	С	R	Α	С		С			
16	3D Control and Planning	1	- 1	R	Α	- 1			С		
17	3D Construction Coordination	- 1	- 1	R	Α	С					
18	Construction System Design	- 1	- 1	R	Α	С		С			
19	Construction Quality Management	- 1	-1	R	Α	-1					С
20	As-Built Model	I	- 1	R	Α	- 1	- 1	- 1	С	- 1	I
21	Maintenance Scheduling	I	I	R	Α	С					
22	Project Systems Analysis	С	- 1	R	Α						
23	Space Management and Tracking	С	- 1	R	Α						
24	Asset Information Model	С	- 1	R	Α	С	- 1	- 1	С	- 1	I
25	Sales and Marketing										
26	Heritage Information Modelling	С	1	R	Α						

BIM Execution Plan Page 56 of 60

# Appendix D – Clash Detection Matrix

	Project n	alli	C																	Upda	ated o	21/12	2/2023
No.	@753r (155.553)	Abbr eviati	ī				2				3	4	5	6	7	8	9	10	11	12	13	14	15
			ARC 1	ARC 2	ARC 3	ARC 4	STR 1	STR 2	STR 3	STR 4	ECS	FSS	PLU	DRN	ELE	SIG	LIG	DfMA	MCS	сом	LIF	UUX	UUP
1	Architecture Model	ARC 1		1	0	19	3	0	4	1	0	2	0	0	0			0		0			
		ARC			112	130	1	8		44		0	0	0	0			0		0			
		ARC				31	2	1.		24	0	0	0	0	0			0		0		0	
		ARC					5	23		71	8	34	4	49	96			0		0		4	
2	Structure Model	4 STR 1						1		2	0	3	0	16	0			0					
		STR 2							0	12		0		0									
									U	1.2		U		,									
		STR 3						0										0		0		0	
	Environmental Control	STR 4									3	25	1	34	20			0		0		19	
3	System Model	ECS									19	1	0	0	0								
4	Fire Services Model	FSS										4	0	0	3								
5	Plumbing Services Model	PLU											4	0	0							2	
6	Drainage Services Model	DRN												4	0					0		23	
7	Electrical Services Model	ELE													11					1		11	
8	Road Sign, Traffic Sign	SIG																		0			
9	Street Light, Street Cable	LIG																		0			
10	Design for Manufacture and Assembly	DfMA																0		0			
11	Main Control System	MCS																		0			
12	Communication System	сом																		0			
13	Lifts	LIF																					
14	Existing Underground Utilities	UUX																					12
15	Proposed Underground Utilities	UUP																					

BIM Execution Plan Page 57 of 60

### Appendix G – Model File List

Discipline	PYC (Full name: Paul Y)	OAP (Full name: ARUP)	Workset					
ARC	11286-W-SUW-PYC-ARC-001 (TBA)	11286-W-SUW-OAP-ARC-001(Baselined)	PYC - CLA - Cladding PYC - GLA - Glazing / CWL - Curtain Wall PYC - LOU - Louvres PYC - CEI - Ceilings PYC - RLS - Railings PYC - GRA - Signage					
FAC	11286-W-SUW-PYC-FAC-001 (TBA)	11286-W-SUW-OAP-FAC-001(Baselined)	PYC - FAC - Façade					
STR	N/A (Non-applicable)	11286-W-SUW-OAP-STR-001 (Action by OAP)	PYC - SFR - Link Bridge PYC - STL - Steel OAP - SFR - Link Bridge OAP - SCO - Concrete OAP - FND - Foundations OAP - STL - Steel					
STR	11286-W-SUW-PYC-STR-020 (Action by Xensetech)		PYC - REB - Pier 1					
STR	11286-W-SUW-PYC-STR-021 (Action by Xensetech)	11286-W-SUW-OAP-STR-002 (Baselined)	PYC - REB - Pier 2-3					
STR	11286-W-SUW-PYC-STR-022 (Action by Xensetech)		PYC - REB - Pier 4					
CIV	N/A (Non-applicable)	11286-W-SUW-TMP-SIT-001 (Baselined)	OAP - TMP - Temporary Works					
CIV	N/A (Non-applicable)	11286-W-SUW-OAP-ELS-001 (Baselined) 11286-W-SUW-OAP-ELS-002 (Baselined)	OAP - ELS - Excavation & Lateral Support					
UUT	11286-W-UUX-PYC-UUT-001 (Action by Xensetech)	11286-W-UUP-OAP-DRN-001 (Action by OAP)	PYC - UUP - Design Underground Utilities OAP - UUP - Design Underground Utilities OAP - UUX - Existing Underground Utilities					
MEP	11286-W-SUW-PYC-MEP-001 (Action by REC)		PYC - DRN - Building Services - Drainage Services PYC - PLU - Building Services - Plumbing Services PYC - DfMA - Design for Manufacture and Assembly					
MEP	11286-W-SUW-PYC-MEP-003 (Action by REC)	11286-W-SUW-OAP-MEP-001	PYC - ECS - Building Services - Environmental Control System PYC - FSS - Building Services - Fire Services					
MEP	11286-W-SUW-PYC-MEP-004 (Action by REC)	(Baselined)	PYC - ELE - Building Services - Electrical Services PYC - SEM - Structural Electrical and Mechanical PYC - C24 - External Works					
COM	11286-W-SUW-PYC-COM-001 (Action by REC)		PYC - COM - E&M Systemwide - Communication System					
LIF	11286-W-SUW-PYC-LIF-001 (Action by TBA)		PYC - LIF - E&M Systemwide - Lifts & Escalators					
MEP	11286-W-SUW-PYC-MEP-002 (Action by REC)	11286-W-SUW-OAP-MEP-002	PYC - EXG - Existing Systems					
MCS	11286-W-SUW-PYC-MCS-001 (Action by REC)	N/A (Non-applicable)	PYC - MCS - E&M Systemwide - Main Control System					

Appendix H – Model Compliance Check Template

### 5.2 Design Review


Design review will be carried out by visual checking and clash detection by software. Clash detection will be performed in the federated model using Navisworks to check design coordination in terms of spatial allowance and interference between disciplines. Clash results will be analysed, recorded, and reported in the format of clash reports and will be reviewed by the corresponding responsible designer(s).

In general, the federated model of Shared individual models will be used for coordination and design review. The federated Shared model will be viewed in design review meetings using Navisworks. These models, along with the associated clash detection results and any recorded coordination issues will be made available on the Client's CDE. All design issues found will be recorded and distributed to all parties that are relevant to their resolution. To facilitate the distribution and tracking of the progress of the design issues, software platforms based on the use of BIM Collaboration – Autodesk Construction Cloud (ACC).


BIM Execution Plan Page 58 of 60

Linear structure modelling approach will be applied to the construction of the SUW Station. The modelling shall start from the placement of objects according to the alignment of the project, setting up the rules and parameters of the trade and preparing a library of the linear structural objects.

For the bridge model, a linear chainage reference will be created to which bridge elements will be set out, in accordance with the design. Depending on the complexity, the bridge elements may be modelled in increasing LOD until LOD-G reaches 300/400 and LOD-I reaches 500. Dynamic envelopes, that may be required for spatial reservation for installation or maintenance reasons, will be incorporated into the model as volumes, at the appropriate time, for design coordination.



BIM Execution Plan Page 59 of 60



The above is presented the flowchart of reporting Issue when issues found, including 5 steps:

- Step 1: The Contractor is responsible for notifying issues found to the Design Consultant in the Autodesk Construction Cloud (ACC) system.
- Step 2: The result of Clash Detection Matrix is performed using Navisworks and BIM Collaboration Function in ACC.
- Step 3: The Design Consultant addresses and resolves the identified issues and provides a response to the Contractor.
- Step 4: The Contractor submits for reviews and checks the provided resolution until the workflow is deemed complete.

~END ~

BIM Execution Plan

Page 60 of 60